

80% FED.
20% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				ROADWAY 0001 URBAN	BRIDGE 0008 S. N. 082-0385	BRIDGE 0008 S. N. 082-0386	BRIDGE 0008 S. N. 082-6003 & 082-0287
50500505	STUD SHEAR CONNECTORS	EACH	3906		1953	1953	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	138610		68790	69820	
50800515	BAR SPLICERS	EACH	174		86	88	
51200959	FURNISHING METAL SHELL PILES 14" X 0.312"	FOOT	2028		1032	996	
51202305	DRIVING PILES	FOOT	2028		1032	996	
51203200	TEST PILE METAL SHELLS	EACH	4		2	2	
51500100	NAME PLATES	EACH	2		1	1	
52100520	ANCHOR BOLTS, 1"	EACH	56		28	28	
542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"	FOOT	82	82			
5421D015	PIPE CULVERTS, CLASS D, TYPE 1 15" (TEMPORARY)	FOOT	40	40			
54213450	END SECTIONS 15"	EACH	2	2			
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2	2			
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	174		86	88	
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	12	12			

Farnsworth
GROUP, INC.
2709 McGraw Drive
Bloomington, Illinois 61704
309-663-8433, 309-663-1571 fax

DESIGNED - JJO	REVISED -
DRAWN - JJO	REVISED -
CHECKED - PJM	REVISED -
DATE - 06/26/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE. 788	SECTION 520-1-2B	COUNTY ST. CLAIR	TOTAL SHEETS 94	SHEET NO. 5
ILLINOIS FED. AID PROJECT				CONTRACT NO. 76F69