

44200934		
CL B PATCH T2 B		
STA. 13+90 RT	9.6 S.Y.	
STA. 14+24 LT	6.4 S.Y.	
STA. 14+28 LT	7.4 S.Y.	
STA. 20+59 RT	14.7 S.Y.	
STA. 32+20 LT	6.8 S.Y.	
STA. 34+33 LT	11.4 S.Y.	
STA. 36+24 LT	8.1 S.Y.	
TOTAL	64.0 S.Y.	

44200942		
CL B PATCH T3 B		
STA. 11+40 LT (SPLIT)	42.4 S.Y.	
STA. 12+49 LT (SPLIT)	45.8 S.Y.	
STA. 19+10 LT (SPLIT)	30.9 S.Y.	
STA. 30+77 R/L (SPLIT)	43.2 S.Y.	
TOTAL	162.0 S.Y.	

44200944		
CL B PATCH T4 B		
STA. 9+08 LT	94.6 S.Y.	
STA. 13+32 LT	71.7 S.Y.	
STA. 14+06 R/T (SPLIT)	118.6 S.Y.	
STA. 14+98 LT	117.8 S.Y.	
STA. 17+20 LT	53.2 S.Y.	
STA. 18+28 LT	30.2 S.Y.	
STA. 38+43 RT	66.1 S.Y.	
TOTAL	552.0 S.Y.	

60218400		
MAN TA 4 DIA T1F CL		
STA. 10+15 LT	1.0 EA.	
TOTAL	1.0 EA.	

60255500		
MAN ADJUST		
STA. 9+13 LT	1.0 EA	
STA. 18+14 LT	1.0 EA	
STA. 20+65 RT	1.0 EA	
STA. 20+65 LT	1.0 EA	
STA. 33+03 LT	1.0 EA	

60255500		
MAN ADJUST (CONT.)		
STA. 34+44 LT	1.0 EA	
STA. 35+05 LT	1.0 EA	
STA. 36+31 LT	1.0 EA	
TOTAL	8.0 EA	

60260100		
INLETS ADJUST		
STA. 12+12 LT	1.0 EA	
STA. 14+75 RT	1.0 EA	
STA. 14+92 LT	1.0 EA	
STA. 18+03 LT	1.0 EA	
STA. 18+11 RT	1.0 EA	
STA. 33+27 LT	1.0 EA	
STA. 34+35 LT	1.0 EA	
STA. 36+28 LT	1.0 EA	
TOTAL	8.0 EA	

60265700		
VV ADJUST		
STA. 9+20 LT	1.0 EA	
STA. 9+45 RT	1.0 EA	
STA. 16+20 LT	1.0 EA	
STA. 34+04 RT	1.0 EA	
STA. 34+10 RT	1.0 EA	
STA. 34+33 LT	1.0 EA	
TOTAL	6.0 EA	

60266600		
VALVE BOX ADJ		
STA. 30+23 LT	1.0 EA	
STA. 32+23 LT	1.0 EA	
STA. 33+23 LT	1.0 EA	
STA. 37+00 LT	1.0 EA	
TOTAL	4.0 EA	

60500040		
REMOV MANHOLES		
STA. 10+15 LT	1.0 EA.	
TOTAL	1.0 EA.	

60605100		
COMB CC&G TB6.24 AEP		
STA. 10+53 RT	222.8 FT	
STA. 15+43 RT	97.2 FT	
STA. 34+24 RT	19.4 FT	
STA. 37+98 LT	37.0 FT	
TOTAL	376.0 FT	

67100100		
MOBILIZATION		
ENTIRE PROJECT	1.0 L.SUM	
TOTAL	1.0 L.SUM	


70300100		
SHORT TERM PAVT MKING		
STA. 8+78 - 9+37	100.0 FT.	
STA. 10+63 - 20+15	576.0 FT.	
STA. 21+48 - 22+50	116.0 FT.	
STA. 30+00 - 33+15	190.0 FT.	
STA. 34+32 - 37+80	225.0 FT.	
TOTAL (3 APPLICATIONS)	3621.0 FT	

70301000		
WORK ZONE PAVEMENT MARKING REMOVAL		
STA. 8+78 - 9+37	33.3 S.F.	
STA. 10+63 - 20+15	192.0 S.F.	
STA. 21+48 - 22+50	38.7 S.F.	
STA. 30+00 - 33+15	63.3 S.F.	
STA. 34+32 - 37+80	75.0 S.F.	
TOTAL	402.0 S.F.	

78000100		
THPL PVT MK LTR & SYM		
STA. 8+88 RT	20.8 S.F.	
STA. 9+04	15.6 S.F.	
STA. 9+16 RT	15.6 S.F.	
STA. 10+84	15.6 S.F.	
STA. 11+31	20.8 S.F.	
STA. 11+77	15.6 S.F.	
STA. 18+58	15.6 S.F.	
STA. 18+97	20.8 S.F.	
STA. 19+30	15.6 S.F.	
STA. 21+55	15.6 S.F.	
STA. 21+73	20.8 S.F.	
STA. 21+89	15.6 S.F.	

78000100		
THPL PVT MK LTR & SYM (CONT.)		
STA. 30+14	20.8 S.F.	
STA. 30+32	15.6 S.F.	
STA. 32+00	15.6 S.F.	
STA. 32+45	20.8 S.F.	
STA. 32+94	15.6 S.F.	
STA. 34+48	15.6 S.F.	
STA. 34+95	20.8 S.F.	
STA. 35+41	15.6 S.F.	
STA. 35+84	15.6 S.F.	
STA. 37+34	15.6 S.F.	
STA. 37+51	20.8 S.F.	
STA. 37+65	15.6 S.F.	
TOTAL	416.0 S.F.	

78000200		
THPL PVT MK LINE 4		
STA. 8+78 - 9+34 LT	117.6 FT.	
STA. 8+78 - 9+34 LT	20.0 FT.	
STA. 8+78 - 9+34 RT	180.0 FT.	
STA. 10+61 - 12+01 LT	280.0 FT.	
STA. 10+63 - 19+50 RT	230.0 FT.	
STA. 10+63 - 19+55	3565.1 FT.	
STA. 11+99 - 19+23 LT	180.0 FT.	
STA. 18+36 - 19+51 RT	115.0 FT.	
STA. 21+48 - 22+50 LT	30.0 FT.	
STA. 21+48 - 21+98 LT	50.0 FT.	
STA. 21+48 - 22+50 RT	30.0 FT.	
STA. 21+48 - 22+50	414.0 FT.	
STA. 30+00 - 33+16	633.2 FT.	
STA. 30+00 - 30+40 LT	40.0 FT.	
STA. 31+65 - 33+10 RT	290.0 FT.	
STA. 31+84 - 33+15 LT	40.0 FT.	
STA. 34+31 - 37+81	701.4 FT.	
STA. 34+35 - 36+14 LT	180.0 FT.	
STA. 34+43 - 36+13 LT	50.0 FT.	
STA. 34+44 - 36+15 RT	50.0 FT.	
STA. 37+35 - 37+75 RT	45.0 FT.	
STA. 39+13 - 39+20	12.6 FT.	
TOTAL	7254.0 FT.	



CITY OF MOLINE
DEPARTMENT OF PUBLIC WORKS - ENGINEERING DIVISION
3635 4TH AVENUE, MOLINE, IL 61265
(309) 524-2350
CITY ENGINEER - SCOTT HINTON, P.E.

AVE. OF THE CITIES RESURFACING
41ST TO 43RD STREET & 41ST ST. 24TH AVE. TO 22ND AVE.
SEC. 12-00253-00-RS

Date	07-02-12	Sheet	4
Scale	1" = 20'	OF	16
Design Engineer	LCK	Contract	85567
Date	09-07-12	Revision	LCK

Date	07-02-12	Sheet	4
Scale	1" = 20'	OF	16
Design Engineer	LCK	Contract	85567