

INFRASTRUCTURE
ENGINEERING
455 E. Adams Street, Suite 104, Peoria, IL 61602
PH: 309.691.1300 FAX: 309.691.1301

			CONSTR. CODE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY
20100500	TREE REMOVAL, ACRES	ACRE	1.25
20200100	EARTH EXCAVATION	CU YD	2,820
20400800	FURNISHED EXCAVATION	CU YD	530
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4,725
25000300	SEEDING, CLASS 3	ACRE	1.25
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	114
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	114
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	114
25100115	MULCH, METHOD 2	ACRE	1.25
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	6,042
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	127
28000305	TEMPORARY DITCH CHECKS	FOOT	490
28000400	PERIMETER EROSION BARRIER	FOOT	3,902
28100109	STONE RIPRAP, CLASS A5	SQ YD	2,083

* SPECIALTY ITEM

FILE NAME * #FILES#	DESIGNED - AJP	REVISED -
USER NAME * IEI	DRAWN - AJP	REVISED -
PLOT SCALE * 2.0000' / 1"	CHECKED - BAR	REVISED -
PLOT DATE * 10/25/2012	DATE - 11/02/2012	REVISED -

PEORIA COUNTY
HIGHWAY DEPARTMENT

SUMMARY OF QUANTITIES

SCALE : N/A SHEET NO. 1 OF 5 SHEETS STA. N/A

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1381	10-00005-03-BR	PEORIA	55	3
			CONTRACT NO. 89464	
ILLINOIS FED. AID PROJ.				