

INFRASTRUCTURE
ENGINEERING
1000 N. W. 11th St., Suite 100
Peoria, IL 61614
TEL: 309.696.1234
FAX: 309.696.1235
www.infrastructure-engineering.com



CONSTR. CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
50300260	BRIDGE DECK GROOVING	SQ YD	677.
50300280	CONCRETE ENCASEMENT	CU YD	6.6
50300300	PROTECTIVE COAT	SQ YD	708
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1
50500505	STUD SHEAR CONNECTORS	EACH	1,212
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	73,060
50800515	BAR SPLICERS	EACH	86
* 50901050	STEEL RAILING, TYPE SM	FOOT	245
51201900	FURNISHING STEEL PILES HP14X89	FOOT	366.5
51202305	DRIVING PILES	FOOT	366.5
51203900	TEST PILE STEEL HP14X89	EACH	2
51500100	NAME PLATES	EACH	1
52100520	ANCHOR BOLTS, 1"	EACH	24
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	76

* SPECIALTY ITEM

FILE NAME * #FILES*	DESIGNED - AJP	REVISED -	PEORIA COUNTY HIGHWAY DEPARTMENT	SUMMARY OF QUANTITIES			F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
USER NAME * IEI	DRAWN - AJP	REVISED -		1381	10-00005-03-BR	PEORIA	55	5			
PLOT SCALE * 2.0000' / 1"	CHECKED - BAR	REVISED -		SCALE: N/A	SHEET NO. 3 OF 5 SHEETS	CONTRACT NO. 89464	ILLINOIS FED. AID PROJ. NO.				
PLOT DATE * 10/29/2012	DATE - 11/02/2012	REVISED -									