

5. SCHEDULE OF EROSION CONTROL

FROM	TO	25100635 HEAVY DUTY EROSION CONTROL BLANKET SQ YD	28000250 TEMPORARY EROSION CONTROL SEEDING POUND	28000305 TEMPORARY DITCH CHECKS FOOT	28000400 PERIMETER EROSION BARRIER FOOT	28100109 STONE RIPRAP, CLASS A5 SQ YD	28200200 FILTER FABRIC SQ YD
SMITHVILLE ROAD							
196+40.20	199+52.75	2,553	54	380	1,594	589	589
200+55.25	203+66.59	3,489	73	110	2,308	111	111
TOTAL		6,042	127	490	3,902	700	700

6. SCHEDULE OF GUARDRAIL RELATED ITEMS

FROM	TO	63000001 STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS FOOT	63100045 TRAFFIC BARRIER TERMINAL, TYPE 2 EACH	63100087 TRAFFIC BARRIER TERMINAL, TYPE 6A EACH	63100167 TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT EACH	63200310 GUARDRAIL REMOVAL FOOT
SMITHVILLE ROAD						
196+40.20	199+52.75	212.5	1	2	1	316
200+55.25	203+66.59	237.5	0	2	2	402
TOTAL		450.0	1	4	3	718

6. SCHEDULE OF GUARDRAIL RELATED ITEMS

FROM	TO	66500105 WOVEN WIRE FENCE, 4' FOOT	78200100 MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR EACH	78201000 TERMINAL MARKER - DIRECT APPLIED EACH	X6330725 STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS) FOOT	X6650202 WOVEN WIRE FENCE REMOVAL FOOT	Z0001002 GUARDRAIL AGGREGATE EROSION CONTROL TON
SMITHVILLE ROAD							
196+40.20	199+52.75	239	7	1	25	243	79
200+55.25	203+66.59	210	6	2	0	210	86
TOTAL		449	13	3	25	453	165

7. SCHEDULE OF PAVEMENT MARKING RELATED ITEMS

FROM	TO	66600105 FURNISHING AND ERECTING RIGHT OF WAY MARKERS EACH	66700205 PERMANENT SURVEY MARKERS, TYPE I EACH	78005110 EPOXY PAVEMENT MARKING - LINE 4" FOOT
SMITHVILLE ROAD				
196+40.20	200+00.00	2	1	337
200+00.00	203+66.59	5	3	337
TOTAL		7	4	675

8. SCHEDULE OF LUMP SUM ITEMS

FROM	TO	67000500 ENGINEER'S FIELD OFFICE, TYPE B CAL MO	67100100 MOBILIZATION L SUM	Z0013798 CONSTRUCTION LAYOUT L SUM	X7010216 TRAFFIC CONTROL AND PROTECTION, (SPECIAL) L SUM
SMITHVILLE ROAD					
196+40.20	203+66.59	6	1	1	1
TOTAL		6	1	1	1

NOTES: SEE STRUCTURAL SHEETS 23 - 37 FOR STRUCTURAL QUANTITIES THAT ARE NOT NOTED THE SCHEDULE OF QUANTITIES.

INFRASTRUCTURE
 ENGINEERING
 485 E. State Street, Suite 101, Peoria, IL 61602
 PH: 309.696.1234 FAX: 309.696.1235

FILE NAME : #FILES#	DESIGNED - AJP	REVISED -	PEORIA COUNTY HIGHWAY DEPARTMENT	SCHEDULE OF QUANTITIES		F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
USER NAME : IEI	DRAWN - AJP	REVISED -				1381	10-00005-03-BR	PEORIA	55	11	
PLOT SCALE : 2.0000 "/>	CHECKED - BAR	REVISED -		SCALE : N/A	SHEET NO. 2 OF 2 SHEETS	STA. N/A	CONTRACT NO. 89464				
PLOT DATE : 10/29/2012	DATE - 11/02/2012	REVISED -		ILLINOIS FED. AID PROJECT							