

SUMMARY OF QUANTITIES			TOTAL QUANTITIES
CODE NO	ITEM	UNIT	
20200100	EARTH EXCAVATION	CU YD	63
20400800	FURNISHED EXCAVATION	CU YD	202
21400100	GRADING AND SHAPING DITCHES	FOOT	1311
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	40
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	82
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	23307
42400800	DETECTABLE WARNINGS	SQ FT	61
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	42
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	71
550A2340	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 18"	FOOT	22

SUMMARY OF QUANTITIES			TOTAL QUANTITIES
CODE NO	ITEM	UNIT	
55100900	STORM SEWER REMOVAL 18"	FOOT	16
60240301	INLETS, TYPE B, TYPE B GRATE	EACH	1
60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	FOOT	42
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	2
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.4
X6050700	REMOVE INLET BOX	EACH	2