



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 8, 2013

SUBJECT: Various Route

Project TE-00D7(058)

Section 11-00033-00-SW (Sullivan)

Moultrie County

Contract No. 95696

Item No. 138, January 18, 2012 Letting

Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 10 of the special provisions
2. Revised sheets 1 and 4 of the plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P. E.
Engineer of Project Management

INLETS, TYPE B, WITH SPECIAL FRAME & GRATE

The inlet shall be in accordance with Article 602.00 of the Standard Specification of Road and Bridge Construction. The special frame and grate shall be Neenah R-2682 or equal. This work shall be paid for the contract unit price for EACH for INLET, TYPE B, WITH SPECIAL FRAME AND GRATE installed as shown in the plans.

CONCRETE STEPS

At two locations, existing concrete steps will have to be removed and replaced per the details shown in the plans. These steps will be formed and poured with regular Portland Cement Concrete. The work shall be paid for the contract unit price for EACH for CONCRETE STEPS constructed.

As shown in the plans concrete steps will parallel the sidewalk at certain locations due to the elevation difference between the building floor elevation and edge of pavement. These steps are to be constructed to the line and grade shown in detail in the plans. These concrete steps will be poured with colored (full depth) Portland Cement Concrete. The treads will be stenciled and the face of the steps will be a smooth finish. The color and stencil shall match and be sealed in accordance to the Portland Cement Concrete Sidewalk 4 Inch Special as stated in these specifications.

At locations noted in the plans a transition wall is shown to separate the different number of steps. These transition walls shall be constructed to the details shown in the plans and shall be included in the cost of the Concrete Steps. Also the steps will be altered at Light Pole foundation locations. The locations around the light pole foundations are detailed in the plans. This work shall also be included in the cost of the concrete steps.

The colored and stenciled steps, transition walls, and alteration around the light pole foundations shall be included in the unit price per SQ FT for CONCRETE STEPS.

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES

This work shall be according to Section 669 of the Standard Specifications and the following:

Revise the second and third sentence of the first paragraph of Article 669.08 to read:
"The affected area shall be monitored with a photo ionization detector (PID) utilizing a lamp of 10.6 eV or greater or an instrument with a flame ionization detector (FID). Any reading on the PID or FID in excess of background levels indicates the potential presence of contaminated material requiring it to be properly managed as either a non-special waste, non-hazardous special waste, or hazardous waste."

Revise the fourth and fifth sentence of the second paragraph of Article 669.08 to read:
"When the analytical results indicate that detected levels are at or below the most stringent maximum allowable concentration (MAC) for chemical constituents in