

# SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	2870
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	793
20200100	EARTH EXCAVATION	CU YD	25819
20200500	EARTH EXCAVATION (WIDENING)	CU YD	2593
20800150	TRENCH BACKFILL	CU YD	1193
25000110	SEEDING, CLASS 1A	ACRE	1.3
25000210	SEEDING, CLASS 2A	ACRE	13
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1287
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1287
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1287
25100115	MULCH, METHOD 2	ACRE	28.6
25100630	EROSION CONTROL BLANKET	SQ YD	4247
28000200	EXCAVATION FOR EROSION CONTROL	CU YD	100
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2860
28000305	TEMPORARY DITCH CHECKS	FOOT	550
28000315	AGGREGATE DITCH CHECKS	TON	120
28000400	PERIMETER EROSION BARRIER	FOOT	5460
28000500	INLET AND PIPE PROTECTION	EACH	44
28000510	INLET FILTERS	EACH	17
28100105	STONE RIPRAP, CLASS A3	SQ YD	104
28100107	STONE RIPRAP, CLASS A4	SQ YD	56
28100203	STONE RIPRAP, CLASS A2	TON	62
28200200	FILTER FABRIC	SQ YD	305
28300400	AGGREGATE DITCH	TON	87
35501310	HOT-MIX ASPHALT BASE COURSE, 6 1/2"	SQ YD	862
35600720	HOT-MIX ASPHALT BASE COURSE WIDENING, 11"	SQ YD	8485
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	764
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	200
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	9276
40600300	AGGREGATE (PRIME COAT)	TON	185

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	3056
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	636
40600990	TEMPORARY RAMP	SQ YD	61
40603087	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 FG, N70	TON	4739
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	3405
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	283
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	510
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	14282
42400800	DETECTABLE WARNINGS	SQ FT	88
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	38117
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	3572
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	50
44000300	CURB REMOVAL	FOOT	213
44000400	GUTTER REMOVAL	FOOT	478
44000600	SIDEWALK REMOVAL	SQ FT	6992
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	92
44201297	DOWEL BARS 1"	EACH	128
44213200	SAW CUTS	FOOT	493
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	25940
48102100	AGGREGATE WEDGE SHOULDERS, TYPE B	TON	400
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	24434
48203100	HOT-MIX ASPHALT SHOULDERS	TON	186
50105220	PIPE CULVERT REMOVAL	FOOT	1755
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2
54001002	BOX CULVERT END SECTIONS, CULVERT NO. 2	EACH	2
54002050	EXPANSION BOLTS 3/4 INCH X 9 INCH	EACH	36
54010404	PRECAST CONCRETE BOX CULVERTS 4' X 4'	FOOT	13
54010909	PRECAST CONCRETE BOX CULVERTS 9' X 9'	FOOT	6
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	48
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	126