

TRAFFIC SIGNAL SCHEDULE

LOCATION	LOCATING UNDERGROUND CABLE FOOT	UNDERGROUND CONDUIT, GALVANIZED STEEL 1 1/2" DIA. FOOT	LIGHT POLE, WOOD, 30 FOOT, CLASS 5 EACH	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C FOOT	RELOCATE EXISTING FLASHING BEACON EACH	REM & REL EXISTING ELECTRICAL SERVICE EACH
LT. STA. 4+42	60	20		30	1	
34' - LT. STA. 4+70			1			1
RT. STA. 133+80	100	3		50	1	
LT. STA. 133+99	40	3		20	1	
TOTAL	200	26	1	100	3	1

SIGNING SCHEDULE

LOCATION	SIGN PANEL -TYPE 1 SQ FT	WOOD SIGN SUPPORT FOOT
26' - LT. STA. 4+42	9- (R1-1)	15
26' - LT. STA. 4+42	2- (W4-4P)	
35' - RT. STA. 4+46	9- (R1-1)	15
35' - RT. STA. 4+46	2- (W4-4P)	
22' - RT. STA. 133+80	9- (R1-1)	17
22' - RT. STA. 133+80	2- (W16-7P)	
22' - LT. STA. 133+99	9- (R1-1)	17
22' - LT. STA. 133+99	2- (W16-7P)	
TOTAL	44	64

SEEDING SCHEDULE

LOCATION	SEEDING CLASS 1A ACRE	SEEDING CLASS 2A ACRE	NITROGEN FERT NUTR POUND	PHOSPHORUS FERT NUTR POUND	POTASSIUM FERT NUTR POUND	MULCH METHOD 2 ACRE	EROSION CONTROL BLANKET SQ YD
STA. 4+02 TO STA. 131+85		13	1170	1170	1170	13	
STA. 131+85 TO STA. 155+75	1.3		117	117	117	1.3	
LT. STA. 14+70 TO STA. 20+40							1731
LT. STA. 32+60 TO STA. 37+30							1666
LT. STA. 41+00 TO STA. 47+50							430
RT. STA. 46+00 TO STA. 48+00							130
LT. STA. 50+00 TO STA. 52+50							290
TOTAL	1.3	13	1287	1287	1287	14.3	4247

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION CU YD	EARTH EXCAVATION (WIDENING) CU YD	EMBANKMENT CU YD	SHRINKAGE (ASSUME 20%) CU YD	ESTIMATED EXCESS EXCAVATION CU YD
4+02 - 155+75	25,819	2,593	13,009	2,602	12,801
TOTAL	25,819	2,593	13,009	2,602	12,801

PAVEMENT MARKING SCHEDULE

LOCATION	SHORT-TERM PAVEMENT MARKING FOOT	WORK ZONE PAVEMENT MARK. REM. SQ FT	THERMOPLASTIC PAVEMENT MARKING					RAISED REFLECTIVE PAVEMENT MARKER EACH	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) EACH
			4"			12"	24"		
			SOLID YELLOW CENTERLINE FOOT	SKIP-DASH YELLOW CENTERLINE FOOT	SOLID WHITE EDGE LINE FOOT	SOLID WHITE FOOT	SOLID WHITE FOOT		
LT. STA. 4+19								24	
RT. STA. 4+19 - STA. 14+50			1031						
RT. STA. 28+75 - STA. 47+25			1850						
RT. STA. 57+50 - STA. 73+50			1600						
RT. STA. 104+25 - STA. 109+00			475						
RT. STA. 126+00 - STA. 155+75			2975						
LT. STA. 4+19 - STA. 23+50			1931						
LT. STA. 37+75 - STA. 56+25			1850						
LT. STA. 66+00 - STA. 82+50			1650						
LT. STA. 113+25 - STA. 118+00			475						
LT. STA. 131+00 - STA. 155+75			2475						
LT. STA. 4+02 - STA. 155+75					15082				
RT. STA. 4+02 - STA. 155+75					14856				
STA. 4+02 - STA. 155+75				2475					
STA. 133+87 TO STA. 133+93						140			
STA. 4+19 TO STA. 155+75	6040	1510					195	3	
PARKING - LT. STA. 133+20			208						
TOTAL	6040	1510	16520	2475	29938	140	24	195	3

GUTTER, CURB & GUTTER, & SIDEWALK SCHEDULE

LOCATION	PCC SIDEWALK 4" SQ FT	DETECTABLE WARNINGS SQ FT	CONCRETE GUTTER, TYPE B FOOT	COMB. CC&G TY B-6.24 FOOT
STA. 13+75 - 20+97			1368	
RT. STA. 31+00 - 38+50			726	
LT. STA. 32+37 - 40+26			736	
LT. STA. 49+00 - 52+50			350	
LT. STA. 59+00 - 60+69			145	
RT. STA. 59+00 - 65+00			573	
RT. STA. 68+70 - 73+00			430	
LT. STA. 111+25 - 122+25			994	
RT. STA. 111+25 - 121+25			974	
LT. STA. 131+85 - 154+21				2177
RT. STA. 132+17 - 154+55				2200
LT. STA. 132+31 - 133+89				183
LT. STA. 136+00	5			
RT. STA. 136+50	5			
LT. STA. 133+90 - 154+21	7016	40		
RT. STA. 133+87 - 154+60	7256	48		
TOTAL	14282	88	6296	4560

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 4 OF 7 SHEETS

ROUTE NO. 548 2733	SECTION 03-00053-01-WR	COUNTY MADISON	TOTAL SHEETS 145	SHEET NO. 14
			CONTRACT NO. 97509	