



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 10, 2019

SUBJECT: FAP Route 305 (Palatine Road)
Project NHPP-JDYP (407)
Section 2018-098-RS & SW
Cook County
Contract No. 62H47
Item No. 9, January 18, 2019 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page ii of the Table of Contents to the Special Provisions
3. Added pages 111 & 112 to the Special Provisions
4. Revised sheets 1,2,4,14 and 15 of the Plans
5. Added sheets 15A-15L to the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger, P.E.".

By: Ted B. Walschleger, P. E.
Engineer of Project Management

MS/al

HOT MIX ASPHALT - PAY FOR PERFORMANCE USING PERCENT WITHIN LIMITS -JOBSITE SAMPLING (BDE).....72
HOT MIX ASPHALT – QUALITY CONTROL FOR PERFORMANCE (BDE)78
HOT-MIX ASPHALT – TACK COAT (BDE).....83
LIGHTS ON BARRICADES (BDE).....84
PAVEMENT MARKING REMOVAL (BDE).....85
PAYMENTS TO SUBCONTRACTORS (BDE)86
PORTLAND CEMENT CONCRETE (BDE)86
PROGRESS PAYMENTS (BDE).....87
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)87
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)99
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....100
TEMPORARY PAVEMENT MARKING (BDE).....100
TRAINING SPECIAL PROVISIONS (BDE)103
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION.105
TRAFFIC CONTROL DEVICES - CONES (BDE).....108
WARM MIX ASPHALT (BDE)108
WEEKLY DBE TRUCKING REPORTS (BDE).....110
WORKING DAYS (BDE)110
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES.....111

Revised 1/10/19

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES

Description. This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

Contract Specific Sites. The excavated soil and groundwater within the areas listed below shall be managed as either “uncontaminated soil”, hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

Intersection of Palatine Road and Linden Avenue, Palatine, Cook County

- All excavation planned at the northwest quadrant, northeast quadrant, southwest quadrant, and southeast quadrant at the intersection of Palatine Road and Linden Avenue. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.09(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of Palatine Road and Ashland Avenue, Palatine, Cook County

- All excavation planned at the northwest quadrant, northeast quadrant, southwest quadrant, and southeast quadrant at the intersection of Palatine Road and Ashland Avenue. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.09(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of Palatine Road and Elmwood Avenue, Palatine, Cook County

- All excavation planned at the northwest quadrant, northeast quadrant, southwest quadrant, and southeast quadrant at the intersection of Palatine Road and Elmwood Avenue. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.09(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of Palatine Road and Greenwood Avenue, Palatine, Cook County

- All excavation planned at the northwest quadrant, northeast quadrant, southwest quadrant, and southeast quadrant at the intersection of Palatine Road and Greenwood Avenue. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.09(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of Palatine Road and Rohlwing Road, Palatine, Cook County

- All excavation planned at the northwest quadrant, northeast quadrant, southwest quadrant, and southeast quadrant at the intersection of Palatine Road and Rohlwing Road. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.09(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Added 1/10/19

Intersection of Palatine Road and Kennicott Boulevard, Palatine, Cook County

- All excavation planned at the northeast quadrant, and southeast quadrant at the intersection of Palatine Road and Kennicott Boulevard. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.09(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of Palatine Road and Arlington Heights Road, Palatine, Cook County

- All excavation planned at the northwest quadrant, and northeast quadrant at the intersection of Palatine Road and Arlington Heights Road. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.09(a)(5). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Additional information on the above sites collected during the Phase I Engineering process is available through the District's Environmental Studies Unit (DESU).

Added 1/10/19