

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				80% FED	80% FED	80% FED
				13% STATE	13% STATE	13% STATE
				3.5% COUNTY	3.5% COUNTY	3.5% COUNTY
		ROADWAY	TRAFFIC SIGNALS	LIGHTING		
		0004	0021	0021		
		URBAN	URBAN	URBAN		
60500060	REMOVING INLETS	EACH	1	1		
60500080	REMOVING CATCH BASINS TO MAINTAIN FLOW	EACH	1	1		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	429	429		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1,085	1,085		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1,220	1,220		
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	579	579		
66300105	CALCIUM CHLORIDE APPLIED	TON	0.9	0.9	△	
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	249	249		
66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2		
66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	LSUM	1	1		
66901002	ON-SITE MONITORING OF REGULATED SUBSTANCES	CAL DAY	18	18		
66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	LSUM	1	1		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5		
67100100	MOBILIZATION	LSUM	1.0	1.0		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		

\* INDICATES SPECIALTY ITEM

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				80% FED	80% FED	80% FED
				13% STATE	13% STATE	13% STATE
				3.5% COUNTY	3.5% COUNTY	3.5% COUNTY
		ROADWAY	TRAFFIC SIGNALS	LIGHTING		
		0004	0021	0021		
		URBAN	URBAN	URBAN		
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1		
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	946	946		
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	421	421		
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	456	456		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3,144	3,144		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	6,301	6,301		
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	120	120		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,576	1,576		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	112	112		
72000100	SIGN PANEL - TYPE 1	SQ FT	78	78		
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	195	195		
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	456	456		

\* INDICATES SPECIALTY ITEM

STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM  
 LICENSE NO. - 384-00121 - EXPIRES 4/30/2019  
 560KAR 11/8/2018  
 FILE NAME: \\crystal.lake\woodman\Projects\Crystal Lake\CRYLC\170562-RT 14 at Virginia\CADD\170562-Sht-S00.dgn



USER NAME = 560KAR	DESIGNED -	REVISED -
PLOT SCALE = 1.0000" = 1/8"	DRAWN -	REVISED -
PLOT DATE = 11/8/2018	CHECKED -	REVISED -
	DATE = 10-04-18	FILE = 170562-Sht-S00.dgn

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: NO SCALE SHEET OF SHEETS STA. TO STA.

△ 1 REV 01-08-19

F.A.P./F.A.U. RTE. 305 0121	SECTION 17-00125-00-CH	COUNTY McHENRY	TOTAL SHEETS 70	SHEET NO. 6
CONTRACT NO. 61F23				
ILLINOIS FED. AID PROJECT QIK31554				