



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 9, 2019

SUBJECT: Route FAU Route 1103 (State and National Parkway)
Section 15-00119-00-PV (Schaumburg)
Cook County
Contract No. 61F00
Item 145
January 18, 2019 Letting
Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Added page 356 to the special provisions**
- 2. Revised page iii of the Index of Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E.
Bureau Chief
Engineer of Design and Environment

A handwritten signature in black ink, reading "Ted B. Walschleger P.E." with a stylized flourish at the end.

By: Ted B. Walschleger, P.E.
Engineer of Project Management

LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET (VOS)	150
LIGHT POLE FOUNDATION, SPECIAL (VOS)	150
TEMPORARY LIGHTING CONTROLLER (VOS)	150
TEMPORARY WOOD POLE (VOS)	151
TEMPORARY LUMINAIRE (VOS)	151
TEMPORARY ELECTRIC SERVICE INSTALLATION (VOS)	155
LIGHT POLE, ALUMINUM, 40 FT. M.H., 8 FT. MAST ARM (MATERIAL ONLY) (VOS)	156
LUMINAIRE, TYPE 1 (MATERIAL ONLY) (VOS)	156
LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8 5/8" X 6' (MATERIAL ONLY) (VOS)	156
BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE (MATERIAL ONLY) (VOS)	157
TRAFFIC SIGNAL GENERAL REQUIREMENTS	158
RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM	169
GROUNDING OF TRAFFIC SIGNAL SYSTEMS	172
COILABLE NON-METALLIC CONDUIT	174
UNDERGROUND RACEWAYS	175
MAINTENANCE OF EXISTING TRAFFIC SIGNAL AND FLASHING BEACON INSTALLATION	176
ELECTRIC CABLE	180
CONCRETE FOUNDATIONS	181
LIGHT EMITTING DIODE (LED) PEDESTRIAN SIGNAL HEAD	182
DETECTOR LOOP	185
RADAR VEHICLE DETECTION SYSTEM	187
PEDESTRIAN PUSH-BUTTON	189
TEMPORARY TRAFFIC SIGNAL INSTALLATION	191
TEMPORARY TRAFFIC SIGNAL TIMING	198
MODIFY EXISTING CONTROLLER CABINET	199
REBUILD EXISTING HANDHOLE	200
REBUILD EXISTING HANDHOLE TO HEAVY-DUTY HANDHOLE	201
RELOCATE EXISTING PEDESTRIAN PUSH-BUTTON	202
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION (TPG)	203
SPECIAL PROVISION FOR INSURANCE (LR 107-4)	205
STORM WATER POLLUTION PREVENTION PLAN	206
USACE PERMIT	221
NCCSWCD PERMIT	234
IDNR FLOODWAY PERMIT	235
MWRD PERMIT	238
LOCAL AGENCY LPC-663 CCDD CERTIFICATION	256
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES	343
I LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8 5/8" X 6' (VOS)	356

LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8 5/8" X 6' (VOS)

Description. This work shall consist of furnishing and installing metal light pole foundations of the bolt circle and shaft size specified and as shown in the plan details. This work shall be according to Section 836 of the Standard Specifications and as modified herein.

Revise the last paragraph of Article 836.03(b) to read:

Grounding electrodes shall be according to Section 806. Ground rod shall be installed through the metal foundation slot and attached to grounding equipment per detail in plans.

Basis of Payment. This item shall be paid for at the contract unit price each for LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8 5/8" x 6'.