

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Various Routes
OVD SIN STR REP & REPL 2007-9
Various Counties
Sheet 40 of 50
Contract Number 44933

District 8
Schedule of Locations for Truss Repair & Replacement

Location No.:	8-01	State I.D. No.:	8S060I055L017.2				
County:	Madison	Route:	I - 55	M.P.:	17.2	Direction:	WB
Description of Work		Unit	Quantity				
REMOVE OVERHEAD SIGN STRUCTURE-SPAN		EACH	1.00				
OVERHEAD SIGN STRUCTURE - SPAN, TYPE II A		FOOT	80.00				
FURNISH & INSTALL METAL SCREEN		EACH	4.00				
DISCONNECT / RECONNECT ELECTRIC SERVICE		EACH	1.00				
REMOVE & REINSTALL SIGN PANEL		SQ FT	472.50				
REMOVE & REINSTALL WALKWAY		FOOT	39.00				
This truss is being downsized from a Type IV truss to a Type II truss. The existing end supports will be used.							
All work must be completed during District 8 non-peak hours.							

Location No.:	8-03	State I.D. No.:	8S060I055L018.3				
County:	Madison	Route:	I - 55	M.P.:	18.3	Direction:	WB
Description of Work		Unit	Quantity				
REMOVE OVERHEAD SIGN STRUCTURE - SPAN		EACH	1.00				
OVERHEAD SIGN STRUCTURE - SPAN, TYPE II A		FOOT	70.00				
FURNISH & INSTALL METAL SCREEN		EACH	4.00				
DISCONNECT / RECONNECT ELECTRIC SERVICE		EACH	1.00				
REMOVE & REINSTALL SIGN PANEL		SQ FT	336.00				
REMOVE & REINSTALL WALKWAY		FOOT	42.00				
This truss is being downsized from a Type IV truss to a Type II truss. The existing end supports will be used.							
All work must be completed during District 8 non-peak hours.							

Location No.:	8-02	State I.D. No.:	8S082S003L004.4				
County:	St. Clair	Route:	IL - 3	M.P.:	4.4	Direction:	SB
Description of Work		Unit	Quantity				
REMOVE OVERHEAD SIGN STRUCTURE - SPAN		EACH	1.00				
OVERHEAD SIGN STRUCTURE - SPAN TYPE IIA		FOOT	84.00				
OVERHEAD SIGN SUPPORT GROUT REPAIR		EACH	4.00				
FURNISH & INSTALL SAFETY CHAIN		EACH	2.00				
DISCONNECT / RECONNECT ELECTRIC SERVICE		EACH	1.00				
REMOVE & REINSTALL SIGN PANEL		SQ FT	377.00				
REMOVE & REINSTALL WALKWAY		FOOT	44.50				
This truss is being downsized from a Type IV truss to a Type II truss. The existing end supports will be used.							
All work must be completed during District 8 non-peak hours.							