

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT		IL 50 @ 207th						
				I000-1A 80% FED 20% STATE	Y031-1F 80% FED 10% STATE 10% VILLAGE	Y031-3D 100% VILLAGE				
20200100	EARTH EXCAVATION	CU YD	10	10						
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2	2						
20400800	FURNISHED EXCAVATION	CU YD	10	10						
20800150	TRENCH BACKFILL	CU YD	3.5	3.5						
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5	5						
21400100	GRADING AND SHAPING DITCHES	FOOT	15	15						
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	0.5	0.5						
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	0.5	0.5						
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	0.5	0.5						
25200100	SODDING	SQ YD	5	5						
25200200	SUPPLEMENTAL WATERING	UNIT	0.5	0.5						
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	2	2						
28200200	FILTER FABRIC	SQ YD	2	2						
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	450	450						
40600535	LEVELING BINDER (HAND METHOD), N70	TON	15	15						
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	22	22						
42101300	PROTECTIVE COAT	SQ YD	720	720						
42400400	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	SQ FT	660	660						
44000100	PAVEMENT REMOVAL	SQ YD	80	80						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1650	1650						
44000600	SIDEWALK REMOVAL	SQ FT	460	460						
44003100	MEDIAN REMOVAL	SQ FT	6075	6075						
50105220	PIPE CULVERT REMOVAL	FOOT	8	8						
54201279	PIPE CULVERTS, TYPE 2 RCCP 24"	FOOT	16	16						
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1						
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	1						
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1						
60604200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	870	870						

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT		IL 50 @ 207th						
				I000-1A 80% FED 20% STATE	Y031-1F 80% FED 10% STATE 10% VILLAGE	Y031-3D 100% VILLAGE				
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	2110	2110						
60619900	CONCRETE MEDIAN, TYPE SB-6.12 (SPECIAL)	SQ FT	1660	1660						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3						
67100100	MOBILIZATION	L SUM	1	1						
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1						
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1						
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	400	400						
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	380	380						
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3900	3900						
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2000	2000						
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	100	100						
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	150	150						
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3300	3300						
* 72000100	SIGN PANEL - TYPE 1	SQ FT	14			14				
* 72000200	SIGN PANEL - TYPE 2	SQ FT	25			25				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	380	380						
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3900	3900						
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2000	2000						
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	100	100						
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	150	150						
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	100	100						
78300100	PAVEMENT MARKING REMOVAL	SQ FT	920	920						
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	70	70						
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	665			665				

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

Rev.

PLOT DATE: 10/25/2006

10/25/2006