

| SUMMARY OF QUANTITIES | | | URBAN TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | | | | |
|-----------------------|---|------|------------------------|---------------------------------|--|-------------------------|--|--|--|
| CODE NO | ITEM | UNIT | | IL 50 @ 207th | | | | | |
| | | | | I000-1A 80% FED 20% STATE | Y031-1F 80% FED 10% STATE 10% VILLAGE | Y031-3D 100% VILLAGE | | | |
| 81000700 | CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL | FOOT | 89 | 89 | | | | | |
| 81001100 | CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL | FOOT | 10 | 10 | | | | | |
| 81018500 | CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL | FOOT | 203 | 203 | | | | | |
| 81018600 | CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL | FOOT | 90 | 90 | | | | | |
| 81018900 | CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL | FOOT | 121 | 121 | | | | | |
| 81019000 | CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL | FOOT | 135 | 135 | | | | | |
| 81400100 | HANDHOLE | EACH | 4 | 4 | | | | | |
| 81400200 | HEAVY-DUTY HANDHOLE | EACH | 4 | 4 | | | | | |
| 81400300 | DOUBLE HANDHOLE | EACH | 2 | 2 | | | | | |
| 81900200 | TRENCH AND BACKFILL FOR ELECTRICAL WORK | FOOT | 759 | 759 | | | | | |
| 85700200 | FULL-ACTUATED CONTROLLER AND TYPE IV CABINET | EACH | 1 | 1 | | | | | |
| 87301215 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C | FOOT | 913 | 913 | | | | | |
| 87301225 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C | FOOT | 1586 | 1586 | | | | | |
| 87301245 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C | FOOT | 1162 | 1162 | | | | | |
| 87301255 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C | FOOT | 1537 | 1537 | | | | | |
| 87301305 | ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR | FOOT | 1600 | 1600 | | | | | |
| 87301805 | ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C | FOOT | 228 | 228 | | | | | |
| 87502480 | TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT. | EACH | 2 | 2 | | | | | |
| 87502500 | TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT. | EACH | 2 | 2 | | | | | |
| 87700150 | STEEL MAST ARM ASSEMBLY AND POLE, 22 FT. | EACH | 1 | 1 | | | | | |
| 87700180 | STEEL MAST ARM ASSEMBLY AND POLE, 28 FT. | EACH | 1 | 1 | | | | | |
| 87700220 | STEEL MAST ARM ASSEMBLY AND POLE, 36 FT. | EACH | 2 | 2 | | | | | |

| SUMMARY OF QUANTITIES | | | URBAN TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | | | | |
|-----------------------|--|--------|------------------------|---------------------------------|--|-------------------------|--|--|--|
| CODE NO | ITEM | UNIT | | IL 50 @ 207th | | | | | |
| | | | | I000-1A 80% FED 20% STATE | Y031-1F 80% FED 10% STATE 10% VILLAGE | Y031-3D 100% VILLAGE | | | |
| 87800100 | CONCRETE FOUNDATION, TYPE A | FOOT | 20 | 20 | | | | | |
| 87800200 | CONCRETE FOUNDATION, TYPE D | FOOT | 4 | 4 | | | | | |
| 87800400 | CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER | FOOT | 60 | 60 | | | | | |
| 88030020 | SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED | EACH | 6 | 6 | | | | | |
| 88030100 | SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED | EACH | 2 | 2 | | | | | |
| 88030110 | SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED | EACH | 2 | 2 | | | | | |
| 88030210 | SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED | EACH | 2 | 2 | | | | | |
| 88102710 | PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED | EACH | 2 | 2 | | | | | |
| 88102740 | PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED | EACH | 3 | 3 | | | | | |
| 88200210 | TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM | EACH | 8 | 8 | | | | | |
| 88500100 | INDUCTIVE LOOP DETECTOR | EACH | 8 | 8 | | | | | |
| 88600100 | DETECTOR LOOP, TYPE I | FOOT | 1166 | 1166 | | | | | |
| 88700200 | LIGHT DETECTOR | EACH | 2 | | 2 | | | | |
| 88700300 | LIGHT DETECTOR AMPLIFIER | EACH | 1 | | 1 | | | | |
| 88800100 | PEDESTRIAN PUSH-BUTTON | EACH | 5 | 5 | | | | | |
| X0322256 | TEMPORARY INFORMATION SIGNING | SQ FT | 103.4 | 103.4 | | | | | |
| X0322903 | SAW CUTTING, (FULL DEPTH) | FOOT | 1745 | 1745 | | | | | |
| X4066426 | BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70 | TON | 22 | 22 | | | | | |
| X4066740 | LEVELING BINDER (HAND METHOD), SUPERPAVE N70 | TON | 15 | 15 | | | | | |
| X7015000 | CHANGEABLE MESSAGE SIGN | CAL MO | 2 | 2 | | | | | |
| *X8050010 | SERVICE INSTALLATION - GROUND MOUNTED | EACH | 1 | 1 | | | | | |
| *X8730027 | ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C | FOOT | 737 | 737 | | | | | |
| *X8730250 | ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED | FOOT | 272 | 272 | | | | | |
| Z0018500 | DRAINAGE STRUCTURES TO BE CLEANED | EACH | 1 | 1 | | | | | |
| 35400542 | PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 15 1/2" | SQ YD | 260 | 260 | | | | | |

* SPECIALTY ITEM

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

Rev.

PLOT DATE: 10/25/2006