

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	2006-027 I	LAKE	31	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
* PARK ROADS		IDNR File No. 2-03-025 D91-401-06		

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	URBAN 100 % STATE	Y025 PARKING				
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	8	8				
20200100	EARTH EXCAVATION	CU YD	394	394				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	117	117				
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1050	1050				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	21	21				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	21	21				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	21	21				
25002014	SEEDING, CLASS 4A (MODIFIED)	ACRE	0.3	0.3				
25200200	SUPPLEMENTAL WATERING	UNIT	11	11				
28000400	PERIMETER EROSION BARRIER	FOOT	13800	13800				
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	17	17				
40600300	AGGREGATE (PRIME COAT)	TON	84	84				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	600	600				
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	2952	2952				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2952	2952				
42101300	PROTECTIVE COAT	SQ YD	757	757				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	6815	6815				
44000600	SIDEWALK REMOVAL	SQ FT	6815	6815				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3				
67100100	MOBILIZATION	L SUM	1	1				
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1000	1000				
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	24260	24260				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	385	385				
X0301339	REMOVE EXISTING PARKING BLOCKS	EACH	622	622				
X0321083	PLASTIC CAR BUMPER	EACH	1300	1300				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	URBAN 100 % STATE	Y025 PARKING				
X0321566	MULCH, SPECIAL	SQ YD	1092	1092				
X0323359	WASHING AND CLEANING	L SUM	1	1				
X2010300	TREE REMOVAL (UNDER 6 UNITS DIAMETER)	UNIT	4	4				
X2110104	TOPSOIL FURNISH AND PLACE, 4" (SPECIAL)	SQ YD	1092	1092				
XX006338	EROSION CONTROL BLANKET (SPECIAL)	SQ YD	1092	1092				
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	1050	1050				

11/2/2006 11:44:08 AM

*** SPECIALTY ITEMS**

Rev. 1-5-07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLOT DATE: 11/3/2006