

CONTRACT NO. 60B74

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
-----------	-------------

1	TITLE SHEET
2-3	LOCATION MAPS
4	INDEX OF SHEETS, STATE STANDARDS, GENERAL NOTES AND SCHEDULE OF QUANTITIES
5	SUMMARY OF QUANTITIES
6-12	DEMOLITION PLANS & SITE CLEANUP PLANS
13-18	LANDSCAPING PLANS
19-25	RIGHT-OF-WAY PLAT OF HIGHWAYS (FOR INFORMATION ONLY)
26-33	BUILDING ASBESTOS LOCATION DETAILS (FOR INFORMATION ONLY)
34	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
35	SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS

STATE STANDARDS

000001	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
701101	OFF ROAD OPERATIONS, MULTILANE LESS THAN 4.5M (15') AWAY FOR SPEEDS > 45 MPH
701106	OFF ROAD OPERATIONS, MULTILANE MORE THAN 4.5M(15') AWAY FOR SPEEDS > 45 MPH
701801	LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
702001	TRAFFIC CONTROL DEVICES

GENERAL NOTES:

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OR BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES. (48 HOUR NOTIFICATION REQUIRED)
- THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, THE CITIES OF JOLIET, LOCKPORT, MCHENRY, CHICAGO, AND VILLAGES OF MUNDELEIN, HAWTHORN WOODS, HANOVER PARK, AND LONG GROVE.
- THE CONTRACTOR WILL NOT BE ABLE TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT THE WRITTEN PERMISSION OF THE DEPARTMENT.
- BARRICADES: THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SANDBAGS ON EACH TYPE I OR TYPE II BARRICADES USED- ONE (1) WEIGHTED SAND BAG ACROSS EACH BOTTOM RAIL.
- BACKFILL USED FOR ANY HOLES, SUCH AS BASEMENTS, SHALL BE FILLED WITH POROUS GRANULAR EMBANKMENT AND SHALL BE INCLUDED IN THE COST OF BUILDING REMOVAL.
- CONTRACTOR IS RESPONSIBLE FOR OBTAINING A DEMOLITION PERMIT FROM THE CITY OR VILLAGE WHERE THE DEMOLITION WILL TAKE PLACE.
- CONTRACTOR MUST CONTACT THE APPROPRIATE CITY OR VILLAGE FOR CORRESPONDING UTILITY DISCONNECTION REQUIREMENTS.
- ALL TRAFFIC CONTROL SHALL BE INCLUDED IN THE PAY ITEMS FOR BUILDING REMOVAL AND DEBRIS REMOVAL.

SCHEDULE OF QUANTITIES

LOCATION	TOPSOIL FURNISH & PLACE, 4" (SQ YD)	SEEDING, CLASS 2 (ACRE)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHORUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)	MULCH, METHOD 1 (ACRE)
LOCATION #1	45	0.01	1.0	1.0	1.0	0.01
LOCATION #2	296	0.10	5.5	5.5	5.5	0.10
LOCATION #3	214	0.04	4.0	4.0	4.0	0.04
LOCATION #4	222	0.05	4.2	4.2	4.2	0.05
LOCATION #5	267	0.06	5.0	5.0	5.0	0.06
LOCATION #6	499	0.10	9.3	9.3	9.3	0.10
LOCATION #8	187	0.04	3.5	3.5	3.5	0.04
LOCATION #9	244	0.10	4.5	4.5	4.5	0.10
TOTAL =	1974	0.50	37	37	37	0.50

REVISED 12/22/06

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
BUILDING DEMOLITION
VARIOUS LOCATIONS
INDEX OF SHEETS STATE STANDARDS
GENERAL NOTES AND
SCHEDULE OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE 12/26/2006

DRAWN BY AA
CHECKED BY