

Y025

Y025

CONTRACT NO. 60B90

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		100% STATE	(PARKING) 50% STATE CITY OF CHICAGO	(PARKING) 50% STATE WORTH TOWNSHIP	(PARKING) CITY OF CHICAGO 100%	(PARKING) WORTH TOWNSHIP 100%
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	21	18	2	1		
40600300	AGGREGATE (PRIME COAT)	TON	100	88	10	2		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	16	13	2	1		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	545	545				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	211	211				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4165	3671	404	90		
42001300	PROTECTIVE COAT	SQ YD	488	428			37	23
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	49577	43855	4652	1070		
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2190	1925			165	100
44002206	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 1 1/2"	SQ YD	2511	2511				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	992	992				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	744	744				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	744	744				
55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500				
60255500	MANHOLES TO BE ADJUSTED	EACH	43	32	11			
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	50	50				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		100% STATE	(PARKING) 50% STATE CITY OF CHICAGO	(PARKING) 50% STATE WORTH TOWNSHIP	(PARKING) CITY OF CHICAGO 100%	(PARKING) WORTH TOWNSHIP 100%
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7658	7658				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	599	599				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	13168	13168				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2774	2774				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	412	412				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	162	162				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	599	599				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13168	13168				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2774	2774				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	412	412				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	235	235				
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	235	235				
88600600	DETECTOR LOOP REPLACEMENT	FOOT	746	746				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2083	1836	202	45		
X6020063	MANHOLES TO BE ADJUSTED WITH NEW FRAME AND PERFORATED LID FOR CATCH BASINS AND MANHOLES, CHICAGO STANDARD	EACH	33	25	8			
Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	28	28				
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	163	163				
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				

\* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
115 TH STREET

11/6/2006 11:56:23 AM