

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	2004-025 RS	LAKE	120	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
* PARK ROADS		IDNR File No. 2-03-025A 091-191-04		

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	ROADWAY I000	JUNCTION CHAMBER Y007	LIGHTING Y030-1E		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	134	134				
20200100	EARTH EXCAVATION	CU YD	8466	8466				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	31	31				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	6780	6780				
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	120	120				
20800150	TRENCH BACKFILL	CU YD	148	90	58			
20900330	GRANULAR BACKFILL	TON	137		137			
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	16828	16807	21			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	352	352				
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	352	352				
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	352	352				
* 25002014	SEEDING, CLASS 4A (MODIFIED)	ACRE	4.5	4	.5			
* 25200200	SUPPLEMENTAL WATERING	UNIT	189	189				
28000400	PERIMETER EROSION BARRIER	FOOT	8420	8420				
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	12	12				
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	868	868				
31102000	SUB-BASE GRANULAR MATERIAL, TYPE C	CU YD	20	20				
35501300	HOT-MIX ASPHALT BASE COURSE, 4"	SQ YD	210	210				
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	868	868				
35501314	HOT-MIX ASPHALT BASE COURSE, 7 1/2"	SQ YD	8642	8637	5			
40600200	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	23	23				
40600300	AGGREGATE (PRIME COAT)	TON	113	113				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	17	17				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1888	1888				
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	620	620				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	4763	4761	2			

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	ROADWAY I000	JUNCTION CHAMBER Y007	LIGHTING Y030-1E		
42101300	PROTECTIVE COAT	SQ YD	770	770				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	5080	5080				
44000100	PAVEMENT REMOVAL	SQ YD	9429	9408	21			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	210	210				
44000600	SIDEWALK REMOVAL	SQ FT	5080	5080				
44004250	PAVED SHOULDER REMOVAL	SQ YD	196	196				
44213200	SAW CUTS	FOOT	135	75	60			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	180	180				
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	235	235				
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	505	505				
50104400	CONCRETE HEADWALL REMOVAL	EACH	1		1			
50104600	CONCRETE RETAINING WALL REMOVAL	FOOT	30	30				
50200100	STRUCTURE EXCAVATION	CU YD	31		31			
50300225	CONCRETE STRUCTURES	CU YD	28		28			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2620		2620			
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2				
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1	1				
54247180	GRATING FOR CONCRETE FLARED END SECTION 42"	EACH	1	1				
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	63	63				
542A1060	PIPE CULVERTS, CLASS A, TYPE 2 15"	FOOT	143	143				
542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	130	130				
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	444	444				
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	16		16			
550A0180	STORM SEWERS, CLASS A, TYPE 1 42"	FOOT	468	452	16			
55101600	STORM SEWER REMOVAL 36"	FOOT	4		4			
55101800	STORM SEWER REMOVAL 42"	FOOT	3		3			
* 56400500	FIRE HYDRANTS TO BE REMOVED	EACH	1	1				
* 56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	1	1				

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
NORTH POINT MARINA

Rev.

PLOT DATE: 10/31/2006