

P.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
342	(G&I2) 1-N-1	LAKE	70	5
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		90% FED 10% STATE URBAN I000-IA	90% FED. 6.7% STATE 3.3% COUNTY TRAFFIC Y031-1F	OPTICOM VILLAGE OF GURNEE 100% Y031-3D
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1275		1275	
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	10		10	
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	2		2	
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1		1	
87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	2		2	
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	4		4	
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	4		4	
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	30		30	
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	15		15	
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	8		8	
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2		2	
88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2		2	
88500100	INDUCTIVE LOOP DETECTOR	EACH	10		10	
88600100	DETECTOR LOOP, TYPE I	FOOT	610		610	
88700200	LIGHT DETECTOR	EACH	3			3
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1			1
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1	
A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	4	4		
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	77.1	77.1		
X0322584	REVTMENT MAT REMOVAL	SQ YD	301	301		
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	693	693		
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	154	154		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		90% FED 10% STATE URBAN I000-IA	90% FED. 6.7% STATE 3.3% COUNTY TRAFFIC Y031-1F	OPTICOM VILLAGE OF GURNEE 100% Y031-3D
X7030130	PAVEMENT MARKING TAPE, TYPE III 4", SPECIAL	FOOT	9896	9896		
X7030140	PAVEMENT MARKING TAPE, TYPE III 6", SPECIAL	FOOT	971	971		
X7030170	PAVEMENT MARKING TAPE, TYPE III LETTER & SYMBOL, SPECIAL	FOOT	548	548		
* X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1	
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	752		752	
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	800			800
XX004068	PORTLAND CEMENT CONCRETE MEDIAN 5"	SQ FT	3110	3110		
XX006198	IMPACT ATTENUATOR, TEMPORARY	EACH	4	4		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Δ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	6	6		
Z0027800	GEOTECHNICAL FABRIC	SQ YD	176	176		
⊙ Z0076600	TRAINEES	HOOR				
XZ068050	STEEL CASINGS 27"	FOOT	130	130		

⊙ Y080
 Δ NON-PARTICIPATING
 * SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES

10/14/2006