

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
342	(G&I2)1-N-1	LAKE	70	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

EARTHWORK SCHEDULE

RTE. 120 @ HUNT CLUB STATIONS	EARTH EXCAVATION PRE-STAGE (CU. YD)	UNSUITABLE MATERIAL (CU.YD.)	EXCAVATION USED AS EMBANKMENT (SHRINKAGE 15%) (CU.YD.)	EMBANKMENT PRE-STAGE (CU. YD.)	EARTH WORK BALANCE SURPLUS (+) OR SHORTAGE (-) (CU. YD.)
92+00 TO 110+00	1188	2138	1009	1287	-278
DRY LAND JACKING & RECIEVING PIT	695				
HUNT CLUB					
11+00 TO 16+00	13	48	11	25	-14
TOTAL	1896	2186	1020	1312	-292

TREE REMOVAL SCHEDULE

STATION	OFFSET/ SIDE (FEET)	TYPE	6 TO 15 UNIT DIAMETER	OVER 15 UNIT DIAMETER
106+25	90' R (WB)	WILLOW	15	
106+25	90' R (WB)	WILLOW	15	
106+25	90' R (WB)	WILLOW	15	
106+25	90' R (WB)	WILLOW	15	
106+25	90' R (WB)	WILLOW		24
106+65	78' R (WB)	WILLOW	12	
108+03	78' R (WB)	WILLOW	14	
108+03	78' R (WB)	WILLOW	14	
108+03	78' R (WB)	WILLOW	14	
108+03	78' R (WB)	WILLOW	14	
108+03	78' R (WB)	WILLOW		16
108+03	78' R (WB)	WILLOW		16
108+07	85' R (WB)	GREEN ASH	12	
109+20	62' R (WB)	WILLOW		16
109+20	62' R (WB)	WILLOW		16
109+20	62' R (WB)	WILLOW		20
109+20	62' R (WB)	WILLOW		20
109+20	62' R (WB)	WILLOW	14	
TOTALS			154	128

NOTE:

A THICKNESS OF 4 INCHES OF TOPSOIL STRIPPING SHALL BE USED FOR REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL.

PLOT DATE = 11/12/2006
 FILE NAME = 11090830.dwg
 PLOT SCALE = 50,000' / IN.
 REFERENCE = REF#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

ROUTE 120
@ HUNT CLUB ROAD
SCHEDULE OF QUANTITIES

SCALE: VERT. DATE

DRAWN BY
CHECKED BY