

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 342	530CRC-PP	COOK	15	7

CONTRACT 62962

**SOUTHBOUND IL RTE. 53 EXTENSION**

PATCH LOCATION NUMBER	LANE	STATION	Southbound			TYPE
			SIZE (L X W)	AREA (SQ. YD.)		
1	2	489+25	8 x 12	10.7	II	
2	2	487+30	6 x 12	8.0	II	
3	2	484+96	14 x 12	18.7	III	
4	2	482+53	26 x 12	34.7	IV	
5	2	481+62	40 x 12	53.3	IV	
6	2	480+98	12 x 12	16.0	III	
7	2	480+31	62 x 12	82.7	IV	
8	2	479+64	14 x 12	18.7	III	
9	2	479+31	14 x 12	18.7	III	
10	2	478+40	40 x 12	53.3	IV	
11	2	477+36	132 x 12	176.0	IV	
12	2	475+95	32 x 12	42.7	IV	
13	2	474+95	10 x 12	13.3	II	
14	2	473+67	14 x 12	18.7	III	
15	2	473+26	10 x 12	13.3	II	
16	2	472+48	106 x 12	141.3	IV	
17	2	471+31	14 x 12	18.7	III	
18	2	469+80	10 x 12	13.3	II	
19	2	468+53	6 x 12	8.0	II	
20	2	468+04	20 x 12	26.7	IV	
21	2	467+43	6 x 12	8.0	II	
22	2	464+79	9 x 12	12.0	II	
23	2	462+93	12 x 12	16.0	III	

**SCHEDULE TOTALS**

CLASS D PATCHES, TYPE II	225 SQ YD
CLASS D PATCHES, TYPE III	285 SQ YD
CLASS D PATCHES, TYPE IV	1470 SQ YD
SAW CUTS	2270 FT

ILLINOIS DEPARTMENT OF TRANSPORTATION

**IL ROUTE 53 EXTENSION  
PAVEMENT PATCHING SCHEDULE  
2 OF 2**