

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5564	111-M-1	WHITESIDE	78	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

80% FED
20% STATE
URBAN
1000-1A

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	80
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	513
20200100	EARTH EXCAVATION	CU YD	5118
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	7403
21400100	GRADING AND SHAPING DITCHES	FOOT	100
* 25100115	MULCH, METHOD 2	ACRE	2.3
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1152
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	11035
* 25000100	SEEDING, CLASS 1	ACRE	1.5
* 25000210	SEEDING, CLASS 2A	ACRE	0.6
* 25000310	SEEDING, CLASS 4	ACRE	0.2
28000300	TEMPORARY DITCH CHECKS	EACH	30
28000400	PERIMETER EROSION BARRIER	FOOT	210
28000500	INLET AND PIPE PROTECTION	EACH	15
31100920	SUB-BASE GRANULAR MATERIAL, TYPE A, 15"	SQ YD	5331
31100935	SUB-BASE GRANULAR MATERIAL, TYPE A, 18"	SQ YD	2029
31100965	SUB-BASE GRANULAR MATERIAL, TYPE A 24"	SQ YD	1311
35101400	AGGREGATE BASE COURSE, TYPE B	TON	873
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	300
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	11.5

* SPECIALTY ITEMS

PLOT DATE = Wed Aug 09 09:22:35 2006
FILE NAME = \\n:\projects\62079\300\487\980\curr.dgn
PLOT SCALE = 56.0000' / IN.
USER NAME = duncant6