

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5564	111-M-1	WHITESIDE	78	14
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS

Location	Sta.	to	Sta.	Sq. Ft.	Remarks
	1537+96.6	--	1540+76.2	124.8	(8) 8' turn arrows
	1541+77.4	--	1544+74.8	124.8	(8) 8' turn arrows
Total =				249.6	

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"

Location	Sta.	to	Sta.	Foot	Remarks
	1527+16.1	--	1532+16.1	125.00	LT - CL skip dash - Yellow
	1527+16.1	--	1532+16.1	500.00	RT - CL solid stripe - Yellow
	1532+16.1	--	1540+76.2	1721.7	Outside median island stripe - Yellow
	1532+60.7	--	1537+35.3	946.6	Inside median island stripe - Yellow
	1541+77.4	--	1549+15.4	1480.3	Outside median island stripe - Yellow
	1545+38.5	--	1549+15.4	752.9	Inside median island stripe - Yellow
	1549+64.1	--	1550+55.1	186.7	Outside median island stripe - Yellow
	1549+64.1	--	1550+11.7	95.8	Inside median island stripe - Yellow
	1550+55.1	--	1555+55.1	125.00	RT - CL skip dash - Yellow
	1550+55.1	--	1555+55.1	500.00	LT - CL solid stripe - Yellow

	1531+73.6	--	1539+65.9	LT	786.3	White Edge Line
	1941+94.7	--	1551+30.6	LT	933.5	White Edge Line
	1531+73.6	--	1540+76.5	RT	907.0	White Edge Line
	1542+72.8	--	1545+54.6	RT	282.7	White Edge Line
	1546+37.9	--	1548+84.2	RT	246.9	White Edge Line
	1549+87.3	--	1551+30.6	RT	144.4	White Edge Line
	17+97.5	--	19+74.2	LT	195.0	White Edge Line
	20+40.8	--	21+84.0	LT	263.4	White Edge Line
	17+97.5	--	19+63.6	RT	276.9	White Edge Line
	20+23.4	--	21+84.0	RT	189.4	White Edge Line
Total =					10659.4	

78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"

Location	Sta.	to	Sta.	Foot	Remarks
	1537+96.0	--	1540+76.1	560.2	2 turn lane stripes - White
	1541+77.3	--	1544+75.1	595.6	2 turn lane stripes - White
Total =				1155.8	

78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"

Location	Sta.	to	Sta.	Foot	Remarks
	1532+16.1	--	1537+66.5	158.3	Median diagonal stripes - Yellow
	1545+07.3	--	1549+15.4	137.2	Median diagonal stripes - Yellow
	1549+64.1	--	1550+55.1	10.1	Median diagonal stripes - Yellow
Total =				305.6	

78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"

Location	Sta.	to	Sta.	Foot	Remarks
	McNeil Road North			29.3	Stop Bar
	McNeil Road South			28.7	Stop Bar
	Kaufman Road South			18.2	Stop Bar
Total =				76.2	

78100100 RAISED REFLECTIVE PAVEMENT MARKER

Location	Sta.	to	Sta.	Each	Remarks
	1532+15.7	--	1532+58.9	2	Two-way Amber
	1532+58.9	--	1537+34.9	24	One-way Amber
	1537+34.9	--	1540+76.1	20	Two-way Amber
	1537+96.1	--	1540+76.1	8	One-way Crystal
	1537+96.1	--	1540+76.1	8	One-way Crystal
	1541+77.4	--	1544+75.1	8	One-way Crystal
	1541+77.4	--	1544+75.1	8	One-way Crystal
	1541+77.4	--	1545+36.5	20	Two-way Amber
	1545+36.5	--	1549+15.4	23	One-way Amber
	1549+64.0	--	1549+77.6	5	One-way Amber
	1549+77.6	--	1550+55.1	4	Two-way Amber
Total =				130	

Z0014800 CULVERT TO BE CLEANED

Location	Sta.	to	Sta.	Foot	Remarks
	24+14.0	--	24+36.0	22	
Total =				22	

X0325519 DRAIN FOR AGGREGATE BASE COURSE

Location	Sta.		Sq. Yd.	Remarks
	1534+50.0	Lt	1.13	
	1534+50.0	Rt	1.10	
	1538+50.0	Lt	1.17	
	1538+50.0	Rt	1.13	
	1542+50.0	Lt	1.13	
	1542+50.0	Rt	1.10	
	1544+50.0	Lt	1.13	
	1544+50.0	Rt	1.10	
	1547+00.0	Lt	1.17	
	1547+00.0	Rt	1.10	
Total =			11.3	

PLOT DATE = Med Dec 18 11:02:24 2006
 FILE NAME = c:\p\o\m\c\207\800\087806-rr.dgn
 PLOT SCALE = 56.0000 / 1 IN.
 USER NAME = grantpm