CONTRACT NO. 64602

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	37-1HBR-1	HENRY	133	6
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

	CODE NUMBER	ITEM	UNITS	URBAN TOTAL	90%-FED 10%-STATE NHS I000 ROADWAY	80%-FED 20%-STATE BR X771-2A BRIDGE
	20100110	TREE REMOVAL (6 TO 15 UNITS)	UNIT	349	349	
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	70.9	70.9	
	20101000	TEMPORARY FENCE	FOOT	1230	1230	
*	20101400	NITROGEN FERTILIZER NUTRIENT	POUND	405.3	405.3	
*	20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	405.3	405.3	
*	20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	405.3	405.3	
	20200100	EARTH EXCAVATION	CU. YD.	9006	9006	
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU. YD.	16.28	16.28	
	20400800	FURNISHED EXCAVATION	CU. YD.	27209	27209	
	20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU. YD.	150		150
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ. YD.	1475	1475	
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ. YD.	27176	27176	
	21301048	EXPLORATION TRENCH 48" DEPTH	FOOT	750	750	
*	251000100	SEEDING, CLASS 1	ACRE	0.12	0.12	
*	25000210	SEEDING, CLASS 2A	ACRE	0.51	0.51	
*	25000310	SEEDING, CLASS 4	ACRE	3.87	3.87	
*	25000750	MOWING	ACRE	4.5	4.5	
*	25100115	MULCH, METHOD 2	ACRE	4.5	4.5	
	25100630	EROSION CONTROL BLANKET	SQ. YD.	8341	8341	
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	5400	5400	
	28000300	TEMPORARY DITCH CHECKS	EACH	70	70	
	28000400	PERIMETER EROSION BARRIER	FOOT	1964	1964	
	28000500	INLET & PIPE PROTECTION	EACH	12	12	
	28100107	STONE RIPRAP, CLASS A4	SQ. YD.	25	25	
	28100109	STONE RIPRAP, CLASS A5	SQ. YD.	64		64
	28200200	FILTER FABRIC	SQ. YD.	89	89	
	31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	5705.16	5705.16	
	35101400	AGGREGATE BASE COURSE, TYPE B	TON	1,887	1,887	
	40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
	40600990	TEMPORARY RAMP	SQ. YD.	293.33	293.33	

*SPECIALTY ITEM

CODE NUMBER	ITEM	UNITS	URBAN TOTAL	90%-FED 10%-STATE NHS I000 ROADWAY	80%-FED 20%-STATE BR X771-2A BRIDGE
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	287.6	287.6	
42001165	BRIDGE APPROACH PAVEMENT	SQ. YD.	214	214	
42001300	PROTECTIVE COAT	SQ. YD.	906.4		906.4
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ. YD.	43.1	43.1	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ. YD.	155	155	
44000100	PAVEMENT REMOVAL	SQ. YD.	2667	2667	
44000700	APPROACH SLAB REMOVAL	SQ. YD.	178	178	
44004300	PAVEMENT BREAKING	SQ. YD.	3343	3343	
44201709	CLASS D PATCHES, TYPE III, 5"	SQ. YD.	16.67	16.67	
48100100	AGGREGATE SHOULDERS, TYPE A	TON	831	831	
48202400	BITUMINOUS SHOULDERS, SUPERPAVE 6"	SQ. YD.	691	691	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1	
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	1	
50102600	CONCRETE REMOVAL	EACH	2		2
50104400	CONCRETE HEADWALL REMOVAL	EACH	4	4	
50105210	REMOVE EXISTING CULVERTS	FOOT	384	384	
50200100	STRUCTURE EXCAVATION	CU. YD.	262		262
50300225	CONCRETE STRUCTURES	CU. YD.	125.2		125.2
50300255	CONCRETE SUPERSTRUCTURE	CU. YD.	243		243
50300260	BRIDGE DECK GROOVING	SQ. YD.	687		687
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L. SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	1908		1908
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	77,320		77,320
51100100	SLOPE WALL 4 INCH	SQ. YD.	262		262
51201610	FURNISHING STEEL PILES HP12X63	FOOT	1627		1627
51203610	TEST PILE STEEL HP12 X 63	EACH	2		2
51500100	NAME PLATES	EACH	1		1
542A1075	PIPE CULVERTS, CLASS A, TYPE 2 30"	FOOT	82	82	
542A1915	PIPE CULVERTS, CLASS A, TYPE 3 30"	FOOT	106	106	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

SUMMARY OF QUANTITIES

PLOT DATE = Tue Sep 12 13:23:06 2006
FILE NAME = c:\pwworking\c23\d0100\c01300\rr.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = renkesij