

| | | | | |
|---------------------|-----------|---------------------------|--------------|-----------|
| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| ..80.. | 37-UHBR-1 | HENRY | 133 | 8 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |

SUMMARY OF QUANTITIES

| CODE NUMBER | ITEM | UNITS | URBAN | | 90%-FED 10%-STATE NHS | 80%-FED 20%-STATE BR |
|-------------|--|-------|---------|-----------------|-----------------------------|----------------------------|
| | | | TOTAL | 1000 ROADWAY | X771-2A BRIDGE | |
| 78201000 | TERMINAL MARKER-DIRECT APPLIED | EACH | 4 | | 4 | |
| 78200530 | BARRIER WALL MARKERS, TYPE C | EACH | 52 | | 52 | |
| Z0002600 | BAR SPLICERS | EACH | 66 | | | 66 |
| Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 | | 1 | |
| Z0020900 | ESTABLISHING AND REFERENCING LAND SECTION MARKERS | EACH | 1 | | 1 | |
| Z0029999 | IMPACT ATTENUATOR REMOVAL | EACH | 28 | | 28 | |
| Z0030030 | IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3 | EACH | 2 | | | 2 |
| Z0030250 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 2 | | | 2 |
| Z0030350 | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 2 | | | 2 |
| Z0049800 | RELOCATE EXISTING SURVEY MARKERS | EACH | 23 | | 23 | |
| Z0069400 | STONE WELLS, SPECIAL | EACH | 4 | | 4 | |
| Z0047300 | PROTECTIVE SHIELD | SQ YD | 455.7 | | | 455.7 |
| A2006714 | TREE, QUERCUS MACROCARPA (BUR OAK), 1 3/4" CALIPER, BALLED AND BURLAPPED | EACH | 20 | | 20 | |
| B2000116 | TREE, ACER CAMPESTRE (HEDGE MAPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED | EACH | 10 | | 10 | |
| B2003714 | TREE, MALUS INDIAN SUMMER (INDIAN SUMMER CRABAPPLE), 1 3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED | EACH | 8 | | 8 | |
| B2005014 | TREE, MALUS SNOWDRIFT (SNOWDRIFT CRABAPPLE), 1-3/4" CALIPER, BALLED AND BURLAPPED | EACH | 8 | | 8 | |
| XX004900 | TURF REINFORCEMENT MAT | SQ YD | 87 | | 87 | |
| X0325278 | DRIVING PILES | FOOT | 1627 | | | 1627 |
| X0325519 | DRAIN FOR AGGREGATE BASE COURSE | SQ YD | 14 | | 14 | |
| X0712400 | TEMPORARY PAVEMENT | SQ YD | 893.5 | | 893.5 | |
| X0919000 | TEMPORARY PAVEMENT REMOVAL | SQ YD | 893.5 | | 893.5 | |
| X4021000 | TEMPORARY ACCESS - PRIVATE ENTRANCE | EACH | 4 | | 4 | |
| X4024000 | TEMPORARY ACCESS - FIELD ENTRANCE | EACH | 3 | | 3 | |
| X4066414 | BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50 | TON | 77.4 | | 77.4 | |
| X4073051 | BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 8-1/2" | SQ YD | 7422.85 | | 7422.85 | |
| X7013015 | TRAFFIC CONTROL FOR ROAD CLOSURE | L SUM | 1 | | 1 | |

* SPECIALTY ITEMS

PLOT DATE: Tue Sep 12 13:23:31 2006
 FILE NAME: c:\projects\2713100\13100evr.dgn
 PLOT SCALE: 50,0000' / IN.
 USER NAME: rnkheelj

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. _____
 HORIZ. _____

DATE _____

DRAWN BY _____
 CHECKED BY _____

SUMMARY OF QUANTITIES