

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	37-IHBR-1	HENRY	133	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

BITUMINOUS SCHEDULE

STATIONING	REMARKS	LENGTH FEET	AVG. WIDTH FEET	MAINLINE AREA SQ. YD.	SHOULDER AREA SQ. YD.	31100100				X4073051	X4066414	48202400	48100100	
						SUBBASE GRANULAR MTL TYPE A				BIT. CONCRETE PAVEMENT SUPERPAVE FULL-DEPTH	BIT. CONC. SURF CSE SP MIX C, N50	BIT. SHOULDERS SP	AGG. SHLDERS TYPE A	
						4"	12"	15"	18"	8.50"	2"	6"	6"	
						TON	TON	TON	TON	SQ. YD.	TON	SQ. YDS	TON	
IL. RTE. 26														
35 + 90 to 36 + 20	Poppy Garden Road LT	30	12.25	40.83	10.00					37.78			0	5
35 + 90 to 36 + 34	Poppy Garden Road RT	44	11.89	58.13	14.67					54.02			0	8
36 + 20 to 38 + 48	Poppy Garden Road LT	228	13.00	329.33	76.00					302.87			0	39
36 + 34 to 37 + 85	Poppy Garden Road RT	151	13.00	218.11	50.33					200.42			0	26
38 + 48 to 40 + 51	Poppy Garden Road LT	203	13.00	293.22	67.67		213.02	2.66		293.22			0	35
37 + 85 to 40 + 44	Poppy Garden Road RT	259	13.00	374.11	86.33		205.65	86.37		374.11			0	44
40 + 51 to 41 + 33	Poppy Garden Road LT	82	13.00	118.44	27.33		87.65			118.44			0	14
40 + 44 to 48 + 60	Poppy Garden Road RT	816	13.00	1178.67	272.00		867.27			1178.67			0	139
41 + 33 to 41 + 97	Poppy Garden Road LT	64	13.00	92.44	21.33		68.00			92.44			0	11
41 + 97 to 43 + 16	Poppy Garden Road LT	119	13.00	171.89	39.67		126.60			171.89			0	20
43 + 16 to 44 + 42	Poppy Garden Road RT	126	13.00	182.00	42.00		134.00			182.00			0	22
44 + 42 to 45 + 38	Poppy Garden Road LT	96	13.00	138.67	32.00		101.70			138.67			0	16
45 + 38 to 50 + 41	Poppy Garden Road LT	503	13.00	726.56	167.67		535.00			726.56	37.1	331	0	0
48 + 60 to 50 + 40.9	Poppy Garden Road RT	180.9	13.00	261.30	60.30		192.54			261.30	11.9	106	0	0
50 + 40.9 to 50 + 70.9	Approach Pavement West	30	26.00	86.67	10.00	29.0	0.00			86.67			0	0
52 + 76.9 to 53 + 6.9	Approach Pavement East	30	26.00	86.67	10.00	29.0	0.00			86.67			0	0
53 + 6.9 to 54 + 88	Poppy Garden Road LT	181.1	13.00	261.59	60.37		192.40			261.59	11.8	105	0	0
53 + 6.9 to 54 + 76	Poppy Garden Road RT	169.1	13.00	244.26	56.37		179.54			244.26	10.9	98	0	0
54 + 88 to 59 + 70.5	Poppy Garden Road LT	482.5	13.00	696.94	160.83		512.80			696.94			0	82
54 + 76 to 59 + 67.5	Poppy Garden Road RT	491.5	13.00	709.94	163.83		521.40			709.94			0	84
59 + 70.5 to 60 + 35	Poppy Garden Road LT	64.5	13.00	93.17	21.50		68.00			93.17			0	11
59 + 67.5 to 60 + 37	Poppy Garden Road RT	69.5	13.00	100.39	23.17		74.36			100.39			0	12
60 + 35 to 63 + 43	Poppy Garden Road LT	308	13.00	444.89	102.67		176.00		226.91	444.89			0	53
60 + 37 to 63 + 26	Poppy Garden Road RT	289	13.00	417.44	96.33		172.64			417.44			0	49
63 + 43 to 63 + 70	Poppy Garden Road LT	27	12.31	36.93	9.00					36.93			0	5
63 + 26 to 63 + 70	Poppy Garden Road RT	44	12.31	60.18	14.67					60.18			0	8
CARROLL STREET														
	GOOD NEIGHBOR POLICY -CTY RD 16	5280	22.00	645.35	3520								0	90
100 + 13 to 101 + 85	Carroll St LT (Stage I)	172	-	236.59	57.33						2.8	25	29	
100 + 13 to 101 + 85	Carroll St RT (Stage II)	172	-	399.11	57.33						2.9	26	29	
GRAND TOTAL				1281.05		58.0	4428.67	684.12	534.47	7422.85	77.4	691	831	

PLOT DATE * Fri Sep 01 16:12:57 2006
 FILE NAME * c:\p\o\m\cts\23180\Ad\3168-vr.dgn
 PLOT SCALE * 50.0000 / IN.
 USER NAME * rama@j

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY
DATE		