

SCHEDULE OF QUANTITIES

F.A.I. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
RD. 37-1HBR-1	HENRY	133	20
STA. _____ TO STA. _____			
FED. ROAD DIST. NO. _____ ILLINOIS		FED. AID PROJECT	

6310085 TRAFFIC BARRIER TERMINAL, TYPE 6

EACH	LOCATION
2	STA. 50+70.90 LT & RT
2	STA. 52+76.90 LT & RT
4	TOTAL

63100167 TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)

EACH	LOCATION
1	STA. 45+53.4 LT
1	STA. 48+78.4 RT
1	STA. 54+69.4 LT
1	STA. 54+56.9 RT
4	TOTAL

63200310 GUARDRAIL REMOVAL

FOOT	LOCATION
590	STA. 44+77 TO 50+69.50 LT
590	STA. 44+77 TO 50+69.50 RT
589	STA. 50+77 TO 58+71 LT
589	STA. 50+77 TO 58+71 RT
221	STA. 459+61.73 TO 461+82 I-80 RT
271	STA. 461+65 TO 464+35 I-80 LT
2850	TOTAL

63500105 DELINEATORS

EACH	LOCATION
2	STA. 100+41.55 LT & RT - AR CULVERT
2	STA. 46+00 LT & RT - AR CULVERT
1	STA. 45+50 LT - TRAFFIC BARRIER TERMINAL
1	STA. 48+51.54 RT - TRAFFIC BARRIER TERMINAL
2	STA. 54+96.25 LT & RT - TRAFFIC BARRIER TERMINAL
2	STA. 60+58.59 LT & RT - AR CULVERT
10	TOTAL

64200105 SHOULDER RUMBLE STRIPS

FOOT	LOCATION
200	STA. 461+50 TO 462+00.0 I-80 LT & RT
200	TOTAL

66500105 WOVEN WIRE FENCE

FOOT	LOCATION
1227	STA. 38+64 TO 50+45
98	STA. 461+15 TO 461+52 I-80 R.O.W. LT
72	STA. 460+87 TO 461+55 I-80 R.O.W. RT
85	STA. 461+92 TO 462+76 I-80 R.O.W. LT
130	STA. 461+90 TO 463+17 I-80 R.O.W. RT
1612	TOTAL

66502000 WOVEN WIRE GATES, 4' X 24' DOUBLE

EACH	LOCATION
1	STA. 39+12 FE - RT
1	TOTAL

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

EACH	LOCATION
1	STA. 38+64.44 29.94' RT
1	STA. 38+64.73 40' RT
1	STA. 39+25.00 40' RT
1	STA. 39+45.61 40' LT
1	STA. 39+45.70 32.18' LT
1	STA. 39+99.82 50' RT
1	STA. 41+22.60 40' LT
1	STA. 41+24.40 50' RT
1	STA. 41+25.00 45' LT
1	STA. 42+75.00 45' LT
1	STA. 43+20.00 60' LT
1	STA. 101+40.51 45' LT
1	STA. 101+61.85 52.89' RT
1	STA. 44+43.86 65' LT
1	STA. 45+00 65' LT
1	STA. 45+00 80' RT
1	STA. 45+33.33 75' LT
1	STA. 48+00 130' RT
1	STA. 48+32.84 75' LT
1	STA. 49+50 145' RT
1	STA. 50+00 85' LT
1	STA. 50+45.15 85' LT
1	STA. 50+46.48 145' RT
1	STA. 52+87.75 115' LT
1	STA. 52+95.86 100' RT
1	STA. 54+00 100' RT
1	STA. 55+00 115' LT
1	STA. 57+00 75' RT
1	STA. 59+00 80' LT
1	STA. 62+40 75' RT
1	STA. 63+50 55' LT
1	STA. 64+20 30' RT
1	STA. 64+25 33' LT
33	TOTAL

CARROLL STREET
CARROLL STREET

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION
1	STA. 38+80 23' RT
1	STA. 48+45 22' RT
1	STA. 60+50 18' RT
3	TOTAL

Plot Date = Mon Dec 02 09:34:58 2008
Plot Scale = 500000 / IN.
User Name = reneal

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. _____
HORIZ. _____

DATE _____

DRAWN BY _____
CHECKED BY _____

SCHEDULE OF QUANTITIES