

SCHEDULE OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
..80.	..37-1HBR-1..	..HENRY..	..133..	..21..
STA.		TO STA.		
FED. ROAD DIST. NO. .		ILLINOIS FED. AID PROJECT		

70300100 SHORT-TERM PAVEMENT MARKING

FOOT	LOCATION				
21	STA. 100+13 TO 102+40	CL	YELLOW SKIP DASH	STAGE I - CARROLL ST	
21	STA. 100+13 TO 102+40	CL	YELLOW SKIP DASH	STAGE II - CARROLL ST	
42	TOTAL				

70300220 TEMPORARY PAVEMENT MARKING - LINE 4"

FOOT	LOCATION				
860	STA. 35+90 TO 44+50	LTEOP	SOLID WHITE		
860	STA. 35+90 TO 44+50	RTEOP	SOLID WHITE		
215	STA. 35+90 TO 44+50	CL	YELLOW SKIP DASH		
621	STA. 44+50.0 TO 50+70.90	LTEOP	SOLID WHITE		
621	STA. 44+50.0 TO 50+70.90	RTEOP	SOLID WHITE		
1093	STA. 52+76.90 TO 63+70	RTEOP	SOLID WHITE		
1093	STA. 52+76.90 TO 63+70	RTEOP	SOLID WHITE		
137.5	STA. 44+50.0 TO 50+00	CL	YELLOW SKIP DASH		
137.5	STA. 44+50.0 TO 50+00	CL	SOLID YELLOW		
600	STA. 50+00 TO 53+00	CL	SOLID DBL YELLOW		
990	STA. 53+00 TO 63+10	CL	SOLID YELLOW		
247.5	STA. 53+00 TO 63+10	CL	YELLOW SKIP DASH		
15	STA. 63+10 TO 63+70	CL	YELLOW SKIP DASH		
195	STA. 43+16 TO 101+85	LTEOP	SOLID WHITE	STAGE III - CARROLL ST	
175	STA. 100+10.0 TO 101+85	CL	SOLID DBL YELLOW	STAGE III - CARROLL ST	
195	STA. 44+42 TO 101+85	RTEOP	SOLID WHITE	STAGE III - CARROLL ST	
8056	TOTAL				

70300520 PAVEMENT MARKING TAPE, TYPE III 4"

FOOT	LOCATION				
1750	STA. 446+00 TO 463+00	RTEOP	SOLID WHITE	I-80 STAGE II	
1800	STA. 460+00 TO 478+00	RTEOP	SOLID WHITE	I-80-STAGE II	
3550	TOTAL				

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ. FT.	LOCATION				
286.67	STA. 35+90 TO 44+50	LTEOP	SOLID WHITE		
286.67	STA. 35+90 TO 44+50	RTEOP	SOLID WHITE		
71.67	STA. 35+90 TO 44+50	CL	YELLOW SKIP DASH		
204.93	STA. 44+50.0 TO 50+70.90	LTEOP	SOLID WHITE		
204.93	STA. 44+50.0 TO 50+70.90	RTEOP	SOLID WHITE		
360.69	STA. 52+76.90 TO 63+70	RTEOP	SOLID WHITE		
360.69	STA. 52+76.90 TO 63+70	RTEOP	SOLID WHITE		
45.38	STA. 44+50.0 TO 50+00	LT CL	YELLOW SKIP DASH		
45.38	STA. 44+50.0 TO 50+00	RT CL	SOLID YELLOW		
198	STA. 50+00 TO 53+00	CL	SOLID DBL YELLOW		
326.7	STA. 53+00 TO 63+10	LT CL	SOLID YELLOW		
81.68	STA. 53+00 TO 63+10	RT CL	YELLOW SKIP DASH		
5	STA. 63+10 TO 63+70	CL	YELLOW SKIP DASH		
7	STA. 100+13 TO 102+40	CL	YELLOW SKIP DASH	STAGE III - CARROLL ST	
578	STA. 446+00 TO 463+50	RTEOP	SOLID WHITE	I-80 STAGE II	
594	STA. 460+00 TO 478+00	RTEOP	SOLID WHITE	I-80-STAGE II	
3657	TOTAL				

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION				
400	STA. 460+50 TO 464+50	STAGE I	I-80 WB-INSIDE LN		
400	STA. 446+00 TO 463+00	STAGE I	I-80 EB-INSIDE LN		
800	TOTAL				

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION				
450	STA. 460+00 TO 464+50	STAGE II	I-80 WB-OUTSIDE LANE		
350	STA. 459+50 TO 463+00	STAGE II	I-80 EB-OUTSIDE LANE		
800	TOTAL				

78001110 PAINT PAVEMENT MARKING - LINE 4"

FOOT	LOCATION				
652	STA. 35+90 TO 43+16	LTEOP	SOLID WHITE		
1258	STA. 44+42 TO 50+70.90	LTEOP	SOLID WHITE		
2186	STA. 52+76.90 TO 63+70	LTEOP	SOLID WHITE		
2962	STA. 35+90 TO 50+70.90	RTEOP	SOLID WHITE		
2186	STA. 52+76.90 TO 63+70	RTEOP	SOLID WHITE		
255	STA. 35+90 TO 41+00	CL	YELLOW SKIP DASH		
450	STA. 41+00 TO 50+00	LT CL	YELLOW SKIP DASH		
1800	STA. 41+00 TO 50+00	RT CL	SOLID YELLOW		
1200	STA. 50+00 TO 53+00	CL	SOLID DBL YELLOW		
2020	STA. 53+00 TO 63+10	LT CL	SOLID YELLOW		
505	STA. 53+00 TO 63+10	RT CL	YELLOW SKIP DASH		
300	STA. 63+10 TO 63+70	CL	YELLOW SKIP DASH		
412	STA. 43+16 TO 101+85	LTEOP	SOLID WHITE		
300	STA. 100+13 TO 101+85	CL	SOLID DBL YELLOW		
402	STA. 100+13 TO 101+85	RTEOP	SOLID WHITE		
16888	TOTAL				

78001180 PAINT PAVEMENT MARKING - LINE 24"

FOOT	LOCATION				
24	STA. 100+20 CARROLL ST.				(WHITE STOP BAR)
24	TOTAL				

78100105 RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)

EACH	LOCATION
1	STA. 51+00.0
1	STA. 51+80.0
1	STA. 52+60.0
3	TOTAL

78200410 GUARDRAIL MARKERS, TYPE A

EACH	LOCATION				
7	STA. 45+50 TO 50+70.90	LT	MONODIRECTIONAL SILVER		
4	STA. 48+51.50 TO 50+70.90	RT	MONODIRECTIONAL SILVER		
4	STA. 52+77.50 TO 54+96.25	LT	MONODIRECTIONAL SILVER		
4	STA. 52+77.50 TO 54+96.25	RT	MONODIRECTIONAL SILVER		
19	TOTAL				

Mon Dec 02 09:58:17 2003
 FILE NAME = 58.80000 / IN.
 PLOT SCALE = 58.80000 / IN.
 USER NAME = renealj

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY

SCHEDULE OF QUANTITIES