

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
505	115BR-1	WINNEBAGO	35	2
STA.		TO STA.		
FED. ROAD DIST. NO. 2		ILLINOIS	FED. AID PROJECT	

GENERAL NOTES

COMMITMENTS

- THE REMOVAL OF BITUMINOUS SURFACING NOT ON A RIGID TYPE BASE REMOVED IN CONJUNCTION WITH THE BASE SHALL BE REMOVED AS EARTH EXCAVATION. THE REMOVAL OF BITUMINOUS SURFACING ON A RIGID TYPE BASE REMOVED IN CONJUNCTION WITH THE BASE SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR PAVEMENT REMOVAL OF THE TYPE SPECIFIED.
- THE FINAL TOP FOUR INCHES OF SOIL IN ANY RIGHT-OF-WAY AREA DISTURBED BY THE CONTRACTOR MUST BE CAPABLE OF SUPPORTING VEGETATION. THE SOIL MUST BE FROM THE A HORIZON (ZERO TO 2' DEEP) OF SOIL PROFILES OF LOCAL SOILS.
- THE CONTRACTOR SHALL SEED ALL DISTURBED AREAS WITHIN THE PROJECT LIMITS. SEEDING CLASS 2A SALT TOLERANT ROAD MIXTURE SHALL BE USED, EXCEPT IN FRONT OF PROPERTIES WHERE THE GRASS WILL BE MOWED, THEN USE SEEDING, CLASS 1 LAWN MIXTURE. THIS WORK WILL BE INCLUDED IN THE CONTRACT UNIT PRICE PER CUBIC YARD FOR EARTH EXCAVATION.
- FERTILIZER SHALL BE APPLIED TO ALL DISTURBED AREAS AND INCORPORATED INTO THE SEEDBED PRIOR TO SEEDING OR PLACEMENT OF SOIL AT THE RATE SPECIFIED IN SECTIONS 250 AND 252 OF THE STANDARD SPECIFICATIONS. THIS WORK SHALL BE INCLUDED IN THE COST OF EARTH EXCAVATION.
- MULCH METHOD 2 SHALL BE APPLIED OVER ALL SEEDED AREAS. THIS SHALL BE INCLUDED IN THE COST OF THE EARTH EXCAVATION.
- PREVIOUSLY PUGMILLED STOCKPILES OF "TYPE A" OLDER THAN 1 MONTH WILL NOT BE APPROVED FOR USE UNTIL A MOISTURE CHECK IS RUN TO VERIFY MOISTURE CONTENT. MATERIAL SHIPPED TO PROJECTS WITHOUT BEING TESTED WILL NOT BE ACCEPTED.
- THE SUBGRADE ON THIS PROJECT, EXCLUSIVE OF ROCK CUT AREAS IS SCHEDULED TO BE IMPROVED TO A 12" DEPTH ACCORDING TO MECHANISTIC PAVEMENT DESIGN. THE AREAS SCHEDULED TO BE IMPROVED TO A DEPTH GREATER THAN 12" ARE ESTIMATED BASED ON THE ORIGINAL GEOTECHNICAL INVESTIGATION. THE SUBGRADE SHALL BE PROCESSED IN ACCORDANCE WITH ARTICLE 301.03 OF THE STANDARD SPECIFICATIONS BEFORE THE ENGINEER SHALL DETERMINE THE LIMITS AND THE ADDITIONAL THICKNESS OF IMPROVEMENT REQUIRED, IF ANY.
- EXCEPT FOR THE TOP 3", ALL AGGREGATE BASES AND SUBBASES 12" IN THICKNESS SHALL BE CONSTRUCTED OF AGGREGATE GRADATION CA-2. IF THE SPECIFIED THICKNESS EXCEEDS 12" THE BASES OR SUBBASES SHALL BE CONSTRUCTED OF TOPSIZE 6" BREAKER-RUN CRUSHED STONE WITH 100% BY WEIGHT, PASSING THE 4" SIEVE AND 15% TO 40% BY WEIGHT, PASSING THE 2" SIZE SIEVE, EXCEPT FOR THE TOP 3". THE BREAKER-RUN CRUSHED STONE SHALL BE REASONABLY UNIFORMLY GRADED FROM COARSE TO FINE AND BE TAKEN FROM A QUARRY LEDGE CAPABLE OF PRODUCING CLASS "D" QUALITY AGGREGATE. THE TOP 3" SHALL BE GRADATION CA-6 OR CA-10 REGARDLESS OF THICKNESS. THE WATER NECESSARY TO ACHIEVE COMPACTION IN ALL BUT THE TOP 3" LAYER MAY BE ADDED AFTER THE SUBBASE OR BASE COURSE IS PLACED ON THE GRADE.

9. THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT:

MIXTURE DESIGN	SURFACE	BINDER	TOP LIFT SHOULDER	BOTTOM LIFTS SHOULDER	BIT. BASE CSE
PG 64-22	PG 64-22	PG 64-22	PG58-22	PG58-22	PG58-22
RAP2 (MAX)	15	25	30	30	30
DESIGN AIR VOIDS	4.2@NSO	4.2@NSO	3@NSO	2@NSO	2@NSO
MIXTURE COMPOSITION (GRADATION MIXTURE)	IL 9.5 OR 12.5	IL 19.0	IL 9.5 OR 12.5	BAM	BAM
FRICITION AGGREGATE	D	N/A	C	N/A	N/A
20 YEAR ESAL	1.5	1.5	N/A	N/A	N/A

- ON FULL DEPTH PAVEMENT, SHOULDER WIDTHS OF 6 FT. OR LESS MAYBE PLACED, AT THE CONTRACTOR'S OPTION, SIMULTANEOUSLY WITH THE ADJACENT TRAFFIC LANE FOR BOTH THE BINDER AND SURFACE COURSE, PROVIDED THE CROSS SLOPE OF BOTH THE PAVEMENT AND SHOULDER CAN BE SATISFACTORILY OBTAINED. THE SHOULDER WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER SQUARE YARD FOR BITUMINOUS SHOULDERS OF THE THICKNESS SPECIFIED ON THE PLANS.
- INSTALL A "TO ACTUATE SIGNAL" SIGN FOR THE TRAFFIC SIGNAL DETECTOR LOOPS. THE DETAIL OF THIS SIGN IS INCLUDED IN THE PLANS. THIS WORK WILL BE INCLUDED IN THE COST OF TRAFFIC CONTROL AND PROTECTION STANDARD 701321.
- BITUMINOUS AND AGGREGATE PRIME COAT SHALL BE PLACED IN ACCORDANCE WITH SECTION 406 OF THE STANDARD SPECIFICATIONS. THE COST OF THE PRIME COATS SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE PER TON FOR BITUMINOUS CONCRETE SURFACE COURSE OF THE TYPE SPECIFIED.
- A NATIONWIDE 404 PERMIT HAS BEEN ISSUED FOR THIS PROJECT AND THE CONDITIONS OF THAT PERMIT MUST BE ADHERED TO.
- THE NEW NUMBER FOR THIS STRUCTURE WILL BE 101-0183.
- THE CONTRACTOR SHALL SUBMIT FOUR COPIES OF THE REQUIRED SHOP DRAWINGS FOR REVIEW AND APPROVAL TO THE BUREAU OF BRIDGES AND STRUCTURES, 2300 SOUTH DIRKSEN PARKWAY, SPRINGFIELD, IL 62764. AFTER APPROVAL OF INITIAL SUBMITTAL, THE CONTRACTOR SHALL SUBMIT ONE SET OF SHOP DRAWINGS TO ERIC HARM, ENGINEER OF MATERIALS, 126 EAST ASH STREET, SPRINGFIELD, IL 62706, AND EIGHT (8) SETS OF SHOP DRAWINGS TO BE DISTRIBUTED TO:
 - DISTRICT 2 DISTRICT ENGINEER (1)
 - FABRICATOR (1)
 - CONTRACTOR (2)
 - RESIDENT ENGINEER (2)
 - DISTRICT 2 BUREAU OF MATERIALS (2)
- THE REVIEW AND APPROVAL OF TEMPORARY SHEET PILING WILL REQUIRE 4 TO 6 WEEKS. THE CONTRACTOR SHALL SCHEDULE HIS WORK ACCORDINGLY.

- THE BORING LOGS FOR THIS STRUCTURE INDICATE THAT GROUNDWATER LEVELS MAY ENCRACH ON THE CONSTRUCTION LIMITS OF THIS STRUCTURE. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO CONTROL THE GROUND WATER AND DIVERT THE STREAM FLOW DURING CONSTRUCTION IN ORDER TO KEEP THE CONSTRUCTION AREA FREE OF WATER. THE METHOD OF CONTROLLING THE WATER SHALL BE SUBJECT TO APPROVAL OF THE ENGINEER AND THE COST SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR THREE-SIDED PRECAST CONCRETE STRUCTURES 36' X 11'.
- CULVERT AND BRIDGE FLOWS MUST BE MAINTAINED THROUGHOUT THE PROJECT. NORMAL FLOW SHALL BE ALLOWED TO PASS AT THE RATE IT ENTERS THE JOBSITE. HIGH FLOWS SHALL BE ALLOWED TO PASS WITHOUT CAUSING DAMAGE TO UPSTREAM PROPERTIES.
- THE CONTRACTOR SHALL SUPPLY THE RESIDENT ENGINEER WITH THE MANUFACTURER'S INSTALLATION REQUIREMENTS FOR THE TYPE OF STEEL PLATE BEAM GUARDRAIL TERMINAL TYPE 1 SPECIAL (TANGENT) OR STEEL PLATE BEAM GUARDRAIL TERMINAL TYPE 1 SPECIAL (FLARED).
- ONE 16D GALVANIZED NAIL SHALL BE USED TO TOE NAIL THE WOOD BLOCK OUT TO THE WOOD POST ON ALL TRAFFIC BARRIER TERMINAL TYPE 1 SPECIALS.
- DELINEATORS SHALL BE INSTALLED AS SHOWN ON STANDARD 635001, EXCEPT THAT THE POST SHALL BE ROTATED 180° AND ONLY METAL-BACKED DELINEATORS SHALL BE PERMITTED.
- DELINEATORS SHALL BE PLACED AT THE ENDS OF APPROACH GUARDRAIL TERMINAL SECTIONS, AND AT EACH HEADWALL OR END SECTION OF AR CULVERTS. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR DELINEATORS.
- PERMANENT SURVEY MARKERS, TYPE II, SHALL BE SET AT INTERVALS OF 1 MILE OR AS DIRECTED BY THE ENGINEER. BRIDGE OR CULVERT PROJECTS SHALL HAVE ONE SURVEY MARKER PLACED NEAR THE STRUCTURE. ESTIMATED: 2 EACH.
- PERMANENT SURVEY MARKERS, TYPE II SHALL BE CAST-IN-PLACE AS SHOWN ON DISTRICT STANDARD 66.2
- THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER A DESCRIPTION OF LOCATION, ELEVATION, AND COORDINATES FOR EACH PERMANENT SURVEY MARKER. THE ENGINEER SHALL SUBMIT THIS INFORMATION TO THE SURVEY CREW.
- WORK ON THIS PROJECT WILL BE IN PROGRESS AT THE SAME TIME AS WORK ON ADJACENT PROJECTS.

WORK ON THESE PROJECTS SHALL BE SCHEDULED TO KEEP INTERFERENCE BETWEEN ALL THE PROJECTS TO A MINIMUM. THE CONTRACTORS SHALL INFORM EACH OTHER OF PROGRESS OF THE PROJECTS AND GIVE FAIR WARNING TO THE OTHER CONTRACTORS WHEN A PROBLEM MIGHT BE ENCOUNTERED.

- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY DURING CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED FOR NON-EMERGENCY WORK. THE JULIE NUMBER IS 800-892-0123. THE FOLLOWING LISTED UTILITIES LOCATED WITHIN THE PROJECT LIMITS OR IMMEDIATELY ADJACENT TO THE PROJECT CONSTRUCTION LIMITS ARE MEMBERS OF JULIE:
 - COMMONWEALTH EDISON CO. ELECTRIC
 - VERIZON TELEPHONE
 - NICOR GAS CO. GAS
 - CHARTER COMM COMMUNICATIONS
- FOLLOWING ARE THE KNOWN UTILITIES LOCATED WITHIN THE PROJECT LIMITS OR IMMEDIATELY ADJACENT TO THE PROJECT CONSTRUCTION LIMITS WHICH ARE NOT MEMBERS OF JULIE AND SHOULD BE NOTIFIED INDIVIDUALLY BY THE CONTRACTOR:
- IDOT-DISTRICT 2 GOVERNMENT
 - 819 DEPOT AVENUE (815) 284-5469
 - DIXON, IL 61021

- THE APPLICABLE PORTIONS OF ARTICLE 105.07 OF THE STANDARD SPECIFICATION SHALL APPLY EXCEPT FOR THE FOLLOWING: THE CONTRACTOR SHALL BE RESPONSIBLE TO LOCATE THE VERTICAL DEPTHS OF THE UNDERGROUND UTILITIES WHICH MAY INTERFERE WITH CONSTRUCTION OPERATIONS. THIS WORK WILL NOT BE MEASURED OR PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED AS INCLUDED IN THE UNIT BID PRICE FOR THE ITEM OF CONSTRUCTION INVOLVED.

PER SB 699 (90 DAY UTILITY RELOCATION LAW), ONCE RIGHT-OF-WAY IS CLEAR TO AWARD THE PROJECT, A NOTICE WILL BE SENT TO THE UTILITY COMPANIES INSTRUCTING THEM TO HAVE THEIR FACILITIES RELOCATED WITHIN 90 DAYS. ESTIMATED DATE RELOCATION COMPLETE = LETTING DATE + 135 DAYS.

- CADD DATA WILL BE AVAILABLE TO CONTRACTORS AND CONSULTANTS WORKING ON THIS PROJECT. THIS INFORMATION WILL BE PROVIDED UPON REQUEST AS MICROSTATION CADD FILES AND GEOPAK COORDINATE GEOMETRY FILES ONLY. IF DATA IS REQUIRED IN OTHER FORMATS IT WILL BE YOUR RESPONSIBILITY TO MAKE THESE CONVERSIONS. IF ANY DISCREPANCY OR INCONSISTENCY ARISES BETWEEN THE ELECTRONIC DATA AND THE INFORMATION ON THE HARD COPY, THE INFORMATION ON THE HARD COPY SHOULD BE USED. CONTACT THE DISTRICT'S PROJECT ENGINEER TO REQUEST THESE FILES.

- BACKFILL MATERIAL SHALL BE INSTALLED AS NOTED ON THE PROVISIONS FOR THREE SIDED PRECAST CONCRETE STRUCTURE. THE BACKFILL MATERIAL GRADATION, COMPACTION AND INSTALLATION METHOD SHALL CONFORM TO THE PRE-CAST STRUCTURE MANUFACTURER'S REQUIREMENTS. THIS WORK SHALL BE INCLUDED IN THE CONTRACT PRICE PER METER (FOOT) FOR THREE SIDED PRECAST CONCRETE STRUCTURES OF THE SIZE SPECIFIED, AS INDICATED IN THE PROVISIONS AND PLAN NOTES.

- THERE ARE TWO JURISDICTIONAL WETLANDS LOCATED WITHIN THE PROJECT AREA, BUT BEYOND THE CONSTRUCTION LIMITS. THESE WILL NOT BE IMPACTED BY PROJECT CONSTRUCTION.
- THESE WETLANDS ARE SHOWN ON THE PLAN SHEET IN THE DESIGN REPORT AND WILL BE SHOWN ON THE CONTRACT PLANS.
- APPROXIMATELY FOUR MONTHS PRIOR TO PROJECT LETTING AND PRIOR TO THE SUBMITTAL OF FINAL PLANS BY THE CONSULTANT TO THE DEPARTMENT, AN INSPECTION OF THE EXISTING STRUCTURE SHALL BE CONDUCTED TO EVALUATE WHETHER STAGE CONSTRUCTION REMAINS FEASIBLE BASED ON THE DETERIORATED CONDITION OF THE DECK BEAMS. RECOMMENDATIONS ON STAGING FEASIBILITY AND REPLACEMENT OF DETERIORATED DECK BEAMS SHOULD BE SUBMITTED TO THE DEPARTMENT'S BRIDGE MAINTENANCE ENGINEER FOR REVIEW AND CONCURRENCE. THE BEAM REMOVAL AND REPLACEMENT PLAN SHOULD BE REVISED AS NECESSARY BASED ON THE RESULTS OF THE INSPECTION. IF IT IS DETERMINED THAT STAGE CONSTRUCTION IS NO LONGER FEASIBLE AND ROAD CLOSURE IS NECESSARY, COORDINATION WITH LOCAL AGENCIES SHOULD BE CONDUCTED PER DEPARTMENT POLICIES.
- ONE MONTH PRIOR TO THE START OF CONSTRUCTION, THE RESIDENT ENGINEER SHALL CONTACT PROPERTY OWNER, MARK SHEDD (815/629-2563), TO ALLOW HIM SUFFICIENT TIME TO REMOVE FENCES CURRENTLY LOCATED ON STATE RIGHT-OF-WAY. MR. SHEDD HAS ALSO REQUESTED A MEETING WITH THE RESIDENT ENGINEER PRIOR TO THE START OF CONSTRUCTION.
- THE CONTRACTOR SHALL CONTACT THE ADJACENT PROPERTY OWNERS ONE (1) WEEK PRIOR TO WORK BEGINNING TO ALLOW FOR ARRANGEMENTS WITH THEIR LIVESTOCK. NOTICE SHALL BE DOCUMENTED AND A COPY GIVEN TO THE RESIDENT ENGINEER. CONSIDERATION AND COOPERATION SHALL BE PROVIDED BETWEEN THE CONTRACTOR AND THE ADJACENT PROPERTY OWNERS AS REQUIRED.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES
FAP 505 (IL 75)
SECTION 115BR-1
WINNEBAGO COUNTY

SCALE: VERT. HORIZ.
DATE 11/05

DRAWN BY NOE
CHECKED BY JKC

PLOT DATE = 4/06
FILE NAME = ZPR0303NOTES.DGN
PLOT SCALE = NONE
USER NAME = CHRIS