

FAP. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
505	115BR-1	WINNEBAGO	26	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

Item No.	Item	Unit	Total QUANTITY	80% FED 20% STATE X028-2A	
				ROADWAY	BRIDGE
20101000	TEMPORARY FENCE	FOOT	360	360	--
20200100	EARTH EXCAVATION	CU YD	249	249	--
20300100	CHANNEL EXCAVATION	CU YD	37	37	--
28000400	PERIMETER EROSION BARRIER	FOOT	155	155	--
28100107	STONE RIPRAP, CLASS A4	SO YD	402	--	402
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SO YD	584	584	--
35101400	AGGREGATE BASE COURSE, TYPE B	TON	85	85	--
35650300	BASE COURSE WIDENING 8"	SO YD	280	280	--
40600990	TEMPORARY RAMP	SO YD	47	47	--
44000100	PAVEMENT REMOVAL	SO YD	344	344	--
48101200	AGGREGATE SHOULDERS, TYPE B	TON	36	36	--
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SO YD	227	227	--
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	--	1
50300225	CONCRETE STRUCTURES	CU YD	74.9	--	74.9
50800105	REINFORCEMENT BARS	POUND	5900	--	5900
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1280	--	1280
51201000	FURNISHING METAL PILE SHELLS 12"	FOOT	2003	--	2003
51202600	DRIVING AND FILLING SHELLS	FOOT	2003	--	2003
51203200	TEST PILE METAL SHELLS	EACH	1	--	1
51205200	TEMPORARY SHEET PILING	SO FT	2046	--	2046
51500100	NAME PLATES	EACH	1	--	1
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	537.5	537.5	--
* 63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	100	100	--
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	75	75	--
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4	--
63200310	GUARDRAIL REMOVAL	FOOT	393	393	--
63500105	DELINEATORS	EACH	4	4	--
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2	--
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MD	4	4	--

Item No.	Item	Unit	Total QUANTITY	80% FED 20% STATE	
				ROADWAY	BRIDGE
67100100	MOBILIZATION	L SUM	1	1	--
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	--
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	--
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	--
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5	--
* 70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	--
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	124	124	--
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1993	1993	--
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	24	24	--
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	754	754	--
70400100	TEMPORARY CONCRETE BARRIER	FOOT	475	475	--
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	475	475	--
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1250	1250	--
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2	2	--
78200410	GUARDRAIL MARKERS, TYPE A	EACH	10	10	--
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	--
78300100	PAVEMENT MARKING REMOVAL	SO FT	417	417	--
X0324032	THREE-SIDED PRECAST CONCRETE STRUCTURES 36' X 11'	FOOT	41.9	--	41.9
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE MIX "C", N50	TON	11	11	--
X4073146	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 13 1/4"	SO YD	533	533	--
Z0002600	BAR SPLICERS	EACH	24	--	24
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	--
28200200	FILTER FABRIC	SO YD	402	--	402
+ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	--
+ Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	--

* SPECIALTY ITEM
 † SFTY-3N

PLOT DATE = 04/08
 FILE NAME = Z891035SUMQUANT
 PLOT SCALE = NONE
 USER NAME = CHHS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAP 505 (IL 75)
 SECTION 115BR-1
 WINNEBAGO COUNTY

SCALE: VERT.
 HORIZ.
 DATE 06/06

DRAWN BY NV
 CHECKED BY JXC