CONTRACT NO. 64940

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
505	115BR-1	WINNEBAGO	35	7
STA. _____		TO STA._____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

STEEL PLATE BEAM GUARD RAIL, TY. A

LOCATION	FOOT
STA 60+56.00 TO STA 62+81.00 (STAGE 1)	225
STA 63+68.50 TO STA 64+81.00 (STAGE 1)	112.5
STA 61+64.50 TO STA 62+77.00 (STAGE 2)	112.5
STA 63+64.50 TO STA 64+52.00 (STAGE 2)	87.5
TOTAL	537.50

STEEL PLATE BEAM GUARD RAIL, TYPE B

LOCATION	FOOT
STA 62+81.00 TO STA 63+06.00 (STAGE 1)	25
STA 63+43.50 TO STA 63+68.50 (STAGE 1)	25
STA 62+77.00 TO STA 63+02.00 (STAGE 2)	25
STA 63+39.50 TO STA 63+64.50 (STAGE 2)	25
TOTAL	100

STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES

LOCATION	FOOT
STA 63+06 TO STA 63+43.5 (STAGE 1)	37.5
STA 63+02 TO STA 63+39.5 (STAGE 2)	37.5
TOTAL	75

TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (TANGENT)

LOCATION	EACH
STA 60+56.00	1
STA 61+64.50	1
STA 64+52.00	1
STA 64+81.00	1
TOTAL	4

GUARDRAIL REMOVAL

LOCATION	FOOT
STA 61+91.15 TO STA 62+92.81 (STAGE 1)	102
STA 63+70.54 TO STA 64+66.67 (STAGE 1)	96
STA 61+79.43 TO STA 62+75.89 (STAGE 2)	97
STA 63+53.89 TO STA 64+52.32 (STAGE 2)	98
TOTAL	393

DELINEATORS

LOCATION	EACH
AT EACH TYPE 1 TERMINAL END	4
TOTAL	4

TEMPORARY BRIDGE TRAFFIC SIGNAL

LOCATION	EACH
STA 59+95 RT	.25
STA 60+20 LT	.25
STA 66+27 RT	.25
STA 66+52 LT	.25
TOTAL	1

SHORT-TERM PAVEMENT MARKING

LOCATION	FOOT
STA. 59+55 TO STA. 67+02	76
STA. 60+60 TO STA. 65+90, LT.	24
STA. 60+60 TO STA. 65+90, RT.	24
TOTAL	124

TEMPORARY PAVEMENT MARKING

	70300220 4"	70300280 24"
LOCATION	FOOT	FOOT
STAGE I	1003	24
STAGE II	990	---
TOTAL	1993	24

WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	SQ FT
SHORT TERM PAVEMENT MARKING	41
TEMPORARY PAVEMENT MARKING	713
TOTAL	754

TEMPORARY CONCRETE BARRIER

LOCATION	FOOT
STA 60+88 TO STA 62+00	112.5
STA 62+00 TO STA 64+50	250
STA 64+50 TO STA 65+62	112.5
TOTAL	475

RELOCATE TEMPORARY CONCRETE BARRIER

LOCATION	FOOT
STA 60+88 TO STA 62+00	112.5
STA 62+00 TO STA 64+50	250
STA 64+50 TO STA 65+62	112.5
TOTAL	475

THERMOPLASTIC PAVEMENT MARKING

	78000200 4" YELLOW	78000200 4" WHITE
LOCATION	FOOT	FOOT
STA 59+55 TO STA 67+02	190	
STA 60+60 TO STA 65+90		1060
TOTAL	1250	

RAISED REFLECTIVE PAVEMENT MARKER

LOCATION	EACH
STA 62+50 TO STA 64+00	2
TOTAL	2

GUARDRAIL MARKER, TYPE A

LOCATION	EACH
LT. STA 61+14.5 TO STA 65+02	4
RT. STA 60+06 TO STA 65+31	6
TOTAL	10

TERMINAL MARKER - DIRECT APPLIED

LOCATION	EACH
STA 60+06.00	1
STA 61+14.50	1
STA 65+02.00	1
STA 65+31.00	1
TOTAL	4

PAVEMENT MARKING REMOVAL

LOCATION	SQ FT
STA. 59+55 TO STA. 67+02	63
STA. 60+60 TO STA. 65+90, LT.	177
STA. 60+60 TO STA. 65+90, RT.	177
TOTAL	417

IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

LOCATION	EACH
STAGE I	2
TOTAL	2

IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

LOCATION	EACH
STAGE II	2
TOTAL	2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
FAP 505 (IL 75)
SECTION 115BR-1
WINNEBAGO COUNTY

SCALE: VERT. HORIZ.
DATE: 12/05
DRAWN BY NOE
CHECKED BY JKC

PLOT DATE = 4/06
FILE NAME = Z:\P1933SCHED
PLOT SCALE = NONE
USER NAME = DOWNS