

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	(2,3,4)BS	WINNEBAGO	46	15
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

78100100 RAISED REFLECTIVE PAVEMENT MARKER

LOCATION	COMMENT	CRYSTAL EACH
US 20 EB		
275 + 75 - 404 + 65	Double markers (80' O.C.)	324
406 + 18 - 411 + 55	Double markers (80' O.C.)	16
413 + 30 - 440 + 30	Double markers (80' O.C.)	70
483 + 10 - 484 + 80	Double markers (80' O.C.)	6
488 + 15 - 493 + 45	Double markers (80' O.C.)	16
497 + 45 - 516 + 88	Double markers (80' O.C.)	50
519 + 28 - 530 + 0	Double markers (80' O.C.)	28
532 + 50 - 540 + 40	Double markers (80' O.C.)	22
571 + 0 - 707 + 11	Double markers (80' O.C.)	342
EB Ramps		
Montague		55
IL 2		48
US 251		53
Alpine		55
I-39 3rd lane		19
US 20 WB		
275 + 75 - 405 + 31	Double markers (80' O.C.)	326
406 + 84 - 413 + 4	Double markers (80' O.C.)	18
414 + 73 - 439 + 4	Double markers (80' O.C.)	62
475 + 63 - 485 + 23	Double markers (80' O.C.)	26
488 + 56 - 493 + 54	Double markers (80' O.C.)	14
497 + 54 - 516 + 90	Double markers (80' O.C.)	50
519 + 30 - 529 + 96	Double markers (80' O.C.)	28
532 + 45 - 546 + 50	Double markers (80' O.C.)	38
575 + 65 - 707 + 11	Double markers (80' O.C.)	330
WB Ramps		
Montague		63
IL 2		57
US 251		60
Alpine		50
TOTAL		2226

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

LOCATION	COMMENT	EACH
US 20 EB		
92 + 50 - IL 2	Mainline	98
IL 2 - US 251	Mainline	63
US 251 - I 39	Mainline	111
EB Ramps		
Montague		48
IL 2		42
US 251		35
Alpine		39
I-39 3rd lane		4
US 20 WB		
92 + 50 - IL 2	Mainline	128
IL 2 - US 251	Mainline	56
US 251 - I 39	Mainline	104
WB Ramps		
Montague		51
IL 2		48
US 251		45
Alpine		35
TOTAL		907

X0322288 MEDIAN CLOSURE

LOCATION	COMMENT	EACH
US 20		
821 + 0	(CROSSOVERS)	1.00
863 + 0	(CROSSOVERS)	1.00
TOTAL		2

X0322392 BEVELED PIPE AND GUARD

LOCATION	COMMENT	EACH
US 20		
819 + 12	(CROSSOVERS)	1.00
861 + 0	(CROSSOVERS)	1.00
TOTAL		2

Z0028415 GEOTECHNICAL REINFORCEMENT

LOCATION	COMMENT	SO YD
US 20 and Ramps		
818 + 12 - 823 + 88	(CROSSOVERS)	1413
860 + 10 - 865 + 90	(CROSSOVERS)	1432
Full depth patches		972.0
TOTAL		3817.0

Z0028700 GRANULAR SUBGRADE REPLACEMENT

LOCATION	COMMENT	CU YD
US 20 and Ramps		
Full depth patches		162.0
TOTAL		162.0

Z0065752 SLOTTED DRAIN, 12", WITH 6" SLOT

LOCATION	COMMENT	FOOT
US 20 and Ramps		
820 + 32 - 821 + 68	(CROSSOVERS)	136
862 + 30 - 863 + 70	(CROSSOVERS)	140
TOTAL		276.0

PLOT DATE = Wed Oct 25 13:59:14 2006
 FILE NAME = P:\AEC\1\6250\running\hemo137\hupass28.tplot.dgn
 PLOT SCALE = 50.0000 / 1 IN.
 USER NAME = rickhewitt

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. _____ HORIZ. _____ DATE _____
DRAWN BY _____		CHECKED BY _____
DATE _____		