

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	12.3.1185	WINNEBAGO	46	19
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS	FED. AID PROJECT	

BITUMINOUS SCHEDULE

STATIONS	LENGTH FT	PROPOSED SURFACE				40600200	40600300	40800050	40600845	40603570	40603310	48101200	40600982	44000158
		PAVEMENT		SHOULDER		BIT. PRIME TON	AGG. PRIME TON	INCIDENTAL HMA SURF TON	P LEV BIND MM N90 TON	P HMA SC "E" N 90 TON	HMA SC "C" N 50 TON	AGG SHLDS TYPE B TON	HMA SURF REM BUTT JT SQ. YD.	HMA SURF REM 2 1/4 INCH SQ. YD.
		WIDTH	SQ. YD.	WIDTH	SQ. YD.									
Westbound														
411 + 85 - 412 + 30	45	24	120.0	15 & Var	55.0	0.08	0.18		1.1	10.1	6.9			175.0
Bridge Omission														
414 + 1 - 414 + 46	45	24	120.0	15 & Var	55.0	0.08	0.18		1.1	10.1	6.9	4.6	100.0	
414 + 46 - 416 + 44	198	24	528.0	15 & Var	242.0	0.33	0.79		29.6	44.4	30.5	20.3		
416 + 44 - 439 + 5	2261	24	6029.3	15	3768.3	4.20	9.04		337.6	506.5	474.8	231.8		
439 + 5 - 448 + 82	977	24	2605.3	4	434.2	1.30	3.91		145.9	218.8	54.7	50.4		
448 + 82 - 449 + 27	45	24	120.0	15	75.0	0.08	0.18		1.1	10.1	9.5	4.6	130.0	
Omission IL 2														
467 + 91 - 468 + 36	45	24	120.0	15	75.0	0.08	0.18		1.1	10.1	9.5	4.6	130.0	
468 + 36 - 475 + 63	727	24	1938.7	4	323.1	0.97	2.91		108.6	162.8	40.7	37.5		
475 + 63 - 484 + 56	893	24	2381.3	15	1488.3	1.66	3.57		133.4	200.0	187.5	91.5		
484 + 56 - 485 + 1	45	24	120.0	15	75.0	0.08	0.18		1.1	10.1	9.5	4.6	130.0	
Bridge Omission														
488 + 35 - 488 + 80	45	24	120.0	15 & Var	55.0	0.08	0.18		1.1	10.1	6.9			175.0
488 + 80 - 490 + 88	208	24	554.7	15 & Var	254.2	0.35	0.83		31.1	46.6	32.0			808.9
490 + 88 - 493 + 4	216	24	576.0	15	360.0	0.40	0.86		32.3	48.4	45.4			936.0
493 + 4 - 493 + 49	45	24	120.0	15	75.0	0.08	0.18		1.1	10.1	9.5			195.0
Bridge Omission														
497 + 49 - 497 + 94	45	24	120.0	15 & Var	55.0	0.08	0.18		1.1	10.1	6.9	4.6	100.0	
497 + 94 - 499 + 63	169	24	450.7	15 & Var	206.6	0.28	0.68		25.2	37.9	26.0	17.3		
499 + 63 - 504 + 85	522	24	1392.0	15	870.0	0.97	2.09		78.0	116.9	109.6	53.5		
504 + 85 - 510 + 95	610	24	1626.7	12	813.3	1.05	2.44		91.1	136.6	102.5			2440.0
510 + 95 - 516 + 44	549	24	1464.0	15	915.0	1.02	2.20		82.0	123.0	115.3	56.3		
516 + 44 - 516 + 89	45	24	120.0	15	75.0	0.08	0.18		1.1	10.1	9.5	4.6	130.0	
Bridge Omission														
519 + 29 - 519 + 74	45	24	120.0	15 & Var	55.0	0.08	0.18		1.1	10.1	6.9	4.6	100.0	
519 + 74 - 520 + 73	99	24	264.0	15 & Var	121.0	0.17	0.40		14.8	22.2	15.2	10.1		
520 + 73 - 529 + 53	880	24	2346.7	15	1466.7	1.64	3.52		131.4	197.1	184.8	90.2		
529 + 53 - 529 + 98	45	24	120.0	15 & Var	55.0	0.08	0.18		1.1	10.1	6.9	4.6	80.0	
Bridge Omission														
532 + 47 - 532 + 92	45	24	120.0	15 & Var	55.0	0.08	0.18		1.1	10.1	6.9	4.6	80.0	
532 + 92 - 533 + 95	103	24	274.7	15 & Var	125.7	0.17	0.41		15.4	23.1	15.8	10.6		
533 + 95 - 535 + 80	185	24	493.3	15	308.3	0.34	0.74		27.6	41.4	38.9	19.0		
535 + 80 - 546 + 50	1070	40 & Var	3644.4	12	1426.7	2.18	5.47		204.1	306.1	179.8	109.7		
546 + 50 - 547 + 54	104	24	277.3	4	46.2	0.14	0.42		15.5	23.3	5.8	5.4		
547 + 54 - 547 + 99	45	24	120.0	15	75.0	0.08	0.18		1.1	10.1	9.5	4.6	143.3	
Omission US 251														
567 + 93 - 568 + 38	45	24	120.0	15	75.0	0.08	0.18		1.1	10.1	9.5	4.6	130.0	
568 + 38 - 575 + 65	727	24	1938.7	4	323.1	0.97	2.91		108.6	162.8	40.7	37.5		
575 + 65 - 596 + 67	2102	24	5605.3	15	3503.3	3.91	8.41		313.9	470.8	441.4	215.5		
596 + 67 - 599 + 20	253	24	674.7	15	421.7	0.47	1.01		37.8	56.7	53.1			1096.3
PAGE TOTALS						23.6	55.1		1979.4	3086.6	2309.3	1107.3	1253.3	5826.2

PLOT DATE = Mon Oct 16 13:46:23 2006
 PLOT SCALE = 50.0000 IN.
 USER NAME = mckleale

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. _____
 HORIZ. _____

DATE _____ DRAWN BY _____
 CHECKED BY _____