

F.A.P. R/E:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	12.3.418S	WINNEBAGO	46	22
STA. _____		TO STA. _____		
FE), ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

# PATCHING SCHEDULE

STATION	WIDTH OF LANE FT	LENGTH OF PATCH		44200970		44200974		44200976		44002214		40601005		44213200	Z0017100	Z0075300	44213100	
		PATCH		CLASS B PATCH TYPE II, 10 INCH		CLASS B PATCH TYPE III, 10 INCH		CLASS B PATCH TYPE IV, 10 INCH		HMA RM OV PATCH 3 1/2		HMA REPL OVER PATCH		SAWING	DOWEL BARS	TIE BARS	PAVEMENT FABRIC	
		LT LANE FT	RT LANE FT	LT LANE SQ. YD.	RT LANE SQ. YD.	LT LANE SQ. YD.	RT LANE SQ. YD.	LT LANE SQ. YD.	RT LANE SQ. YD.	LT LANE SQ. YD.	RT LANE SQ. YD.	LT LANE TONS	RT LANE TONS	(3W+FL) (feet)	(each)	(each)	SQ YD	
EB Continued																		
492 + 91	12	6	6	8.0	8.0						9.33	9.33	1.83	1.83	90	40		
497 + 74	12	6	6	8.0	8.0						9.33	9.33	1.83	1.83	90	40		
498 + 52	12	15	15			20.0	20.0				21.33	21.33	4.18	4.18	117	40		40.0
499 +	12	8	8	10.7	10.7						12.00	12.00	2.35	2.35	96	40		
500 + 2	12	6	6	8.0	8.0						9.33	9.33	1.83	1.83	90	40		
515 + 12	12	10	10	13.3	13.3						14.67	14.67	2.87	2.87	102	40		
515 + 91	12	6	6	8.0	8.0						9.33	9.33	1.83	1.83	90	40		
519 + 90	12	39	39					52.0	52.0		53.33	53.33	10.45	10.45	189	40	19	104.0
527 + 34	12	6	6	8.0	8.0						9.33	9.33	1.83	1.83	90	40		
528 + 16	12	8	8	10.7	10.7						12.00	12.00	2.35	2.35	96	40		
528 + 96	12	15	15			20.0	20.0				21.33	21.33	4.18	4.18	117	40		40.0
533 + 36	12	15	15			20.0	20.0				21.33	21.33	4.18	4.18	117	40		40.0
534 + 17	12	6	6	8.0	8.0						9.33	9.33	1.83	1.83	90	40		
534 + 96	12		6		8.0							9.33		1.83	48	20		
594 + 48	12	8	8	10.7	10.7						12.00	12.00	2.35	2.35	96	40		
601 + 8	12	8	8	10.7	10.7						12.00	12.00	2.35	2.35	96	40		
614 + 4	12	8	8	10.7	10.7						12.00	12.00	2.35	2.35	96	40		
631 + 70	12	8	8	10.7	10.7						12.00	12.00	2.35	2.35	96	40		
673 + 24	12	8	8	10.7	10.7						12.00	12.00	2.35	2.35	96	40		
696 + 24	12	6	6	8.0	8.0						9.33	9.33	1.83	1.83	90	40		
WB																		
296 + 22	12	8	8	10.7	10.7						12.00	12.00	2.35	2.35	96	40		
296 + 94	12	6	6	8.0	8.0						9.33	9.33	1.83	1.83	90	40		
316 + 30	12	6	6	8.0	8.0						9.33	9.33	1.83	1.83	90	40		
327 + 13	12	6	6	8.0	8.0						9.33	9.33	1.83	1.83	90	40		
336 + 7	12	8	8	10.7	10.7						12.00	12.00	2.35	2.35	96	40		
354 + 69	12	8	8	10.7	10.7						12.00	12.00	2.35	2.35	96	40		
367 + 69	12	8	8	10.7	10.7						12.00	12.00	2.35	2.35	96	40		
384 + 52	12	8	8	10.7	10.7						12.00	12.00	2.35	2.35	96	40		
391 + 59	12	8	8	10.7	10.7						12.00	12.00	2.35	2.35	96	40		
402 + 35	12	10	10	13.3	13.3						14.67	14.67	2.87	2.87	102	40		
PAGE SUB-TOTAL				245.3	253.3	60.0	60.0	52.0	52.0	396.0	405.3	77.6	79.4	2940.0	1180.0	19.0	224.0	
FULL DEPTH PAGE SUBTOTAL (40% of sub-total)				98.1	101.3	24.0	24.0	20.8	20.8									

PLOT DATE : Mon, Dec 16 10:45:55 2008  
 FILE NAME : P:\CADD\PROJECTS\winnebago\1371\tpass22\tpass22.dgn  
 PLOT SCALE : 50.0000' / IN.  
 USER NAME : mckleale

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_

DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_