

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	12.3.4185	WINNEBAGO	46	23
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PATCHING SCHEDULE

STATION	WIDTH OF LANE FT	LENGTH OF PATCH		44200970		44200974		44200976		44002214		40601005		44213200	Z0017100	Z0075300	44213100	
		PATCH		CLASS B PATCH TYPE II, 10 INCH		CLASS B PATCH TYPE III, 10 INCH		CLASS B PATCH TYPE IV, 10 INCH		HMA RM OV PATCH 3 1/2		HMA REPL OVER PATCH		SAWING	DOWEL BARS	TIE BARS	PAVEMENT FABRIC	
		LT LANE	RT LANE	LT LANE	RT LANE	LT LANE	RT LANE	LT LANE	RT LANE	LT LANE	RT LANE	LT LANE	RT LANE	(3W+FL)	(each)	(each)	SQ YD	
		FT	FT	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	TONS	TONS	(feet)				
WB Continued																		
404 + 17	12		37					49.3			50.67		9.93	110	20.00	18.00	49.33	
411 + 57	12		8	8	10.7	10.7				12.00	12.00	2.35	2.35	96	40.00			
412 + 49	12			6		8.0					9.33		1.83	48	20.00			
418 + 23	12		8	8	10.7	10.7				12.00	12.00	2.35	2.35	96	40.00			
424 + 59	12			6		8.0					9.33		1.83	48	20.00			
435 + 58	12		8	8	10.7	10.7				12.00	12.00	2.35	2.35	96	40.00			
483 + 17	12		15	15			20.0	20.0		21.33	21.33	4.18	4.18	117	40.00		40.00	
484 + 70	12		6	6	8.0	8.0				9.33	9.33	1.83	1.83	90	40.00			
489 + 2	12		6	6	8.0	8.0				9.33	9.33	1.83	1.83	90	40.00			
489 + 65	12		6	6	8.0	8.0				9.33	9.33	1.83	1.83	90	40.00			
490 + 14	12		8	8	10.7	10.7				12.00	12.00	2.35	2.35	96	40.00			
492 + 17	12		8	8	10.7	10.7				12.00	12.00	2.35	2.35	96	40.00			
492 + 33	12		6	6	8.0	8.0				9.33	9.33	1.83	1.83	90	40.00			
493 + 4	12		6	6	8.0	8.0				9.33	9.33	1.83	1.83	90	40.00			
497 + 90	12		6	6	8.0	8.0				9.33	9.33	1.83	1.83	90	40.00			
498 + 53	12		6	6	8.0	8.0				9.33	9.33	1.83	1.83	90	40.00			
498 + 84	12		6	6	8.0	8.0				9.33	9.33	1.83	1.83	90	40.00			
499 + 20	12		15	15			20.0	20.0		21.33	21.33	4.18	4.18	117	40.00		40.00	
515 + 25	12		8	8	10.7	10.7				12.00	12.00	2.35	2.35	96	40.00			
516 + 13	12		6	6	8.0	8.0				9.33	9.33	1.83	1.83	90	40.00			
520 + 4	12		6	6	8.0	8.0				9.33	9.33	1.83	1.83	90	40.00			
520 + 35	12		6	6	8.0	8.0				9.33	9.33	1.83	1.83	90	40.00			
522 + 25	12		8	8	10.7	10.7				12.00	12.00	2.35	2.35	96	40.00			
528 + 30	12		8	8	10.7	10.7				12.00	12.00	2.35	2.35	96	40.00			
529 + 19	12		6	6	8.0	8.0				9.33	9.33	1.83	1.83	90	40.00			
533 + 15	12		20	20					26.7	26.7	28.00	28.00	5.49	5.49	132	40.00	9.00	53.33
535 + 31	12		8	8	10.7	10.7				12.00	12.00	2.35	2.35	96	40.00			
535 + 68	12		6		8.0					9.33		1.83		48	20.00			
576 + 51	12		8	8	10.7	10.7				12.00	12.00	2.35	2.35	96	40.00			
592 + 60	12		8	8	10.7	10.7				12.00	12.00	2.35	2.35	96	40.00			
607 + 92	12		8	8	10.7	10.7				12.00	12.00	2.35	2.35	96	40.00			
620 + 14	12		8	8	10.7	10.7				12.00	12.00	2.35	2.35	96	40.00			
PAGE SUB-TOTAL					242.7	250.7	40.0	40.0	76.0	26.7	398.7	357.3	78.1	70.0	2948.0	1200.0	27.0	182.7
FULL DEPTH PAGE SUBTOTAL (40% of sub-total)					97.1	100.3	16.0	16.0	30.4	10.7								

PLOT DATE = Mon Oct 16 13:45:24 2006
 FILE NAME = P:\Econ\US206\winnebago\379\ypass20\ypass20.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = nickleale

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. _____
 HORIZ. _____

DATE _____

DRAWN BY _____
 CHECKED BY _____