

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
635	(105)BR-2	KANKAKEE	25	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES				← 80% FED 20% STATE →	
CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTR. TYPE CODE	
				ROADWAY I000	Y007
20200100	EARTH EXCAVATION	CU YD	41.0	41.0	
20400800	FURNISHED EXCAVATION	CU YD	185.0	185.0	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	205.0		205.0
• 25000300	SEEDING, CLASS 3	ACRE	0.3	0.3	
• 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	26.0	26.0	
• 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	26.0	26.0	
• 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	26.0	26.0	
• 25100115	MULCH, METHOD 2	ACRE	0.3	0.3	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	84.0	84.0	
28000300	TEMPORARY DITCH CHECKS	EACH	4.0	4.0	
35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	185.0	185.0	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	191.0	191.0	
40600300	AGGREGATE (PRIME COAT)	TON	3.0	3.0	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	347.0	347.0	
40600990	TEMPORARY RAMP	SQ YD	40.0	40.0	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	14.0	14.0	
44000100	PAVEMENT REMOVAL	SQ YD	98.0	98.0	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	35.0	35.0	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1.0	1.0	
50105210	REMOVE EXISTING CULVERTS	FOOT	58.0	58.0	
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	125.0	125.0	
54011104	PRECAST CONCRETE BOX CULVERT 11' X 4'	FOOT	48.0		48.0
54215550	METAL END SECTIONS 15"	EACH	4.0	4.0	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	416.0	416.0	
63200310	GUARDRAIL REMOVAL	FOOT	348.0	348.0	
67100100	MOBILIZATION	L SUM	1.0	1.0	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1.0	1.0	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	1.0	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1.0	1.0	

• SPECIALTY ITEMS

SUMMARY OF QUANTITIES