

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
635	(105)BR-2	KANKAKEE	25	4
STA.		TO STA.		
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				

SUMMARY OF QUANTITIES				← 80% FED 20% STATE →	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR TYPE CODE	
				ROADWAY I000	Y007
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	200.0	200.0	
70300220	TEMPORARY PAVEMENT MARKING- LINE 4"	FOOT	1290.0	1290.0	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	162.0	162.0	
• 70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1252.0	1252.0	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	458.0	458.0	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	286.0	286.0	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	170.0	170.0	
• 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1290.0	1290.0	
• 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	162.0	162.0	
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	8.0	8.0	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	215.0	215.0	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	8.0	8.0	
X0324043	GRATING FOR CONCRETE HEADWALL	EACH	2.0		2.0
35501320	HOT-MIX ASPHALT BASE COURSE 9"	SQ YD	543.0	543.0	
35501332	HOT-MIX ASPHALT BASE COURSE 12"	SQ YD	185.0	185.0	
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX'D, N90	TON	210.0	210.0	
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	105.0	105.0	
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1.0	1.0	
■ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2.0	2.0	
■ Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2.0	2.0	
Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	10.0	10.0	
X0325582	PRECAST BOX CULVERT END SECTION 11' X 4'	FOOT	2.0		2.0

- SPECIALTY ITEMS
- SFTY-3N

SUMMARY OF QUANTITIES