

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
840	139 BR-2	KANKAKEE	69	52
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

PAY CODE	DESCRIPTION	UNIT	TOTAL	CONSTRUCTION TYPE CODE	
				Y007	1000
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	23		23
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	22		22
20200100	EARTH EXCAVATION	CU YD	784		784
20300100	CHANNEL EXCAVATION	CU YD	40	40	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	201	201	
2101505	TOPSOIL EXCAVATION & PLACEMENT	CU YD	480		480
25000210	SEEDING, CLASS 2A	ACRE	0.75		0.75
25000400	NITROGEN FERTILIZER NUTRIENTS	POUND	70		70
25000500	PHOSPHORUS FERTILIZER NUTRIENTS	POUND	70		70
25000600	POTASSIUM FERTILIZER NUTRIENTS	POUND	70		70
2510015	MULCH, METHOD 2	ACRE	0.75		0.75
28000100	TEMPORARY DITCH CHECKS	EACH	10		10
28000500	SEEDING, CLASS 7	ACRE	2.25		2.25
28100107	STONE RIPRAP, CLASS A4	SQ YD	715	233	482
28200200	FILTER FABRIC	SQ YD	715	233	482
31100110	SUB-BASE GRANULAR MATERIAL, TYPE A, 12"	SQ YD	220		220
35500130	HOT-MIX ASPHALT BASE COURSE, 11 1/2"	SQ YD	189		189
40200800	AGGREGATE SURFACE COURSE, TY B	TON	98		98
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	243		243
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	175		175
40800982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	406		406
40803340	HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	191		191
44000100	PAVEMENT REMOVAL	SQ YD	127		127
44101500	AGGREGATE SHOULDERS, TYPE B, 6"	SQ YD	671		671
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
50105200	REMOVE EXISTING CULVERTS	EACH	3		3
54001000	BOX CULVERT END SECTIONS	EACH	2	2	
54020707	PRECAST CONCRETE BOX CULVERT 7'x7' (M273)	FOOT	108	108	

PAY CODE	DESCRIPTION	UNIT	TOTAL	CONSTRUCTION TYPE CODE	
				Y007	1000
54200220	PIPE CULVERTS, CLASS D, TY 1, 15"	FOOT	82		82
54200223	PIPE CULVERTS, CLASS D, TY 1, 18"	FOOT	52		52
54213450	END SECTIONS, 15"	EACH	4		4
54213453	END SECTIONS, 18"	EACH	2		2
63200310	GUARDRAIL REMOVAL	FOOT	598		598
66600105	FURNISHING & ERECTING RIGHT-OF-WAY MARKERS	EACH	8		8
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4		4
67100100	MOBILIZATION	L SUM	0.5		0.5
70100150	TRAFFIC CONTROL & PROTECTION STANDARD 701201	L SUM	0.5		0.5
70100160	TRAFFIC CONTROL & PROTECTION STANDARD 701306	L SUM	0.5		0.5
70100385	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	20		20
78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	1354		1354
78001130	PAINT PAVEMENT MARKING-LINE 6"	FOOT	170		170
78000100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	8		8
78000200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	8		8
70101005	TRAFFIC CONTROL & PROTECTION FOR TEMPORARY DETOUR	L SUM	1		1

* - SPECIALITY ITEM

PLOT DATE = 10/27/2006
 FILE NAME = 840252.DWG
 REFERENCE = 840252

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAP ROUTE 840 (US 45/52)
 SEC 139 BR-2, KANKAKEE COUNTY

SUMMARY OF QUANTITIES

SCALE: VERT. _____
 DATE: _____

DRAWN BY _____
 CHECKED BY _____