

80% FED  
20% STATE

SUMMARY OF QUANTITIES		UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
CODE #	PAY ITEM			I000-2A ROADWAY	X020-2A #053-0182 STRUCTURE
20200100	EARTH EXCAVATION	CU YD	239	239	
20400800	FURNISHED EXCAVATION	CU YD	44	44	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	78		78
25000210	SEEDING, CLASS 2A	ACRE	0.2	0.2	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	14	14	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	14	14	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	14	14	
25100115	MULCH, METHOD 2	ACRE	0.2	0.2	
25100630	EROSION CONTROL BLANKET	SQ YD	89	89	
28000300	TEMPORARY DITCH CHECKS	EACH	4	4	
28000400	PERIMETER EROSION BARRIER	FOOT	1,342	1,342	
28100107	STONE RIPRAP, CLASS A4	SQ YD	569		569
28200200	FILTER FABRIC	SQ YD	569		569
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1,301	1,301	
40200900	AGGREGATE SURFACE COURSE, TYPE B	CU YD	1	1	
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	207	207	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	64	64	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	217	217	
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	244	244	
42001300	PROTECTIVE COAT	SQ YD	244	244	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	50	50	
44000100	PAVEMENT REMOVAL	SQ YD	32	32	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL 1 1/2"	SQ YD	1,406	1,406	
44000700	APPROACH SLAB REMOVAL	SQ YD	160	160	
44004250	PAVED SHOULDER REMOVAL	SQ YD	1,345	1,345	
48101200	AGGREGATE SHOULDERS TYPE B	TON	20	20	
48203023	HOT-MIX ASPHALT SHOULDERS 6 1/2"	SQ YD	1,169	1,169	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50200100	STRUCTURE EXCAVATION	CU YD	201		201
50300100	FLOOR DRAINS	EACH	8		8
50300225	CONCRETE STRUCTURES	CU YD	140.6		140.6
50300255	CONCRETE SUPERSTRUCTURE	CU YD	223.4		223.4
50300260	BRIDGE DECK GROOVING	SQ YD	392		392
50300280	CONCRETE ENCASEMENT	CU YD	9.8		9.8
50300300	PROTECTIVE COAT	SQ YD	503		503
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	61,300		61,300
50800515	BAR SPLICERS	EACH	257		257

\* SPECIALTY ITEM

80% FED  
20% STATE

SUMMARY OF QUANTITIES		UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
CODE #	PAY ITEM			I000-2A ROADWAY	X020-2A #053-0182 STRUCTURE
51201600	FURNISHING STEEL PILES HP 12x53	FOOT	1,557		1,557
51202305	DRIVING PILES	FOOT	1,557		1,557
51203600	TEST PILE STEEL HP 12x53	EACH	2		2
51205200	TEMPORARY SHEET PILING	SQ FT	252		252
51500100	NAME PLATES	EACH	1		1
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	43		43
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	154		154
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	300	300	
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	630	630	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3,753	3,753	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	48	48	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	906	906	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	375	375	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	325	325	
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1,538	1,538	
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	290	290	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	6	6	
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2	2	
78200410	GUARDRAIL MARKERS - TYPE A	EACH	6	6	
78200520	BARRIER WALL MARKERS - TYPE B	EACH	4	4	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	340	340	
XX003404	TEMPORARY PAVEMENT, 8"	SQ YD	822	822	
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON - REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON - REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	24		24

\* SPECIALTY ITEM ■ SFTY-3N



Excellence through Ownership

200 West Front Street  
Wheaton, IL 60187

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.P. ROUTE 41 (IL 17)

**SUMMARY OF QUANTITIES**

SCALE: VERT.  
HORIZ.  
DATE: OCTOBER 20, 2006

DRAWN BY: NEC  
CHECKED BY: SPF