


SUMMARY OF QUANTITIES					80% FED 20% STATE	
CODE #	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				1000-2A	X071-2A	
				ROADWAY	#053-0183 STRUCTURE	
20200100	EARTH EXCAVATION	CU YD	320	320		
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	83		83	
25000210	SEEDING, CLASS 2A	ACRE	0.1	0.1		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	5	5		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	5	5		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	5	5		
25100115	MULCH, METHOD 2	ACRE	0.1	0.1		
25100630	EROSION CONTROL BLANKET	SQ YD	7	7		
28000300	TEMPORARY DITCH CHECKS	EACH	4	4		
28000400	PERIMETER EROSION BARRIER	FOOT	381	381		
28100107	STONE RIPRAP, CLASS A4	SQ YD	875		875	
28200200	FILTER FABRIC	SQ YD	875		875	
31100300	SUB-BASE GRANULAR MATERIAL - TYPE A 4"	SQ YD	794	794		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	164	164		
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	74	74		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	348	348		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	176	176		
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	220	220		
42001300	PROTECTIVE COAT	SQ YD	220	220		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	44	44		
44000100	PAVEMENT REMOVAL	SQ YD	125	125		
44000700	APPROACH SLAB REMOVAL	SQ YD	176	176		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	61	61		
48203023	HOT-MIX ASPHALT SHOULDERS 6 1/2"	SQ YD	670	670		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1	
50200100	STRUCTURE EXCAVATION	CU YD	296		296	
50300100	FLOOR DRAINS	EACH	12		12	
50300225	CONCRETE STRUCTURES	CU YD	94.5		94.5	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	134.8		134.8	
50300260	BRIDGE DECK GROOVING	SQ YD	358		358	
50300280	CONCRETE ENCASEMENT	CU YD	8.4		8.4	
50300300	PROTECTIVE COAT	SQ YD	472		472	

\* SPECIALTY ITEM

SUMMARY OF QUANTITIES					80% FED 20% STATE	
CODE #	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				1000-2A	X071-2A	
				ROADWAY	#053-0183 STRUCTURE	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1	
50500505	STUD SHEAR CONNECTORS	EACH	2,448		2,448	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	38,230		38,230	
50800515	BAR SPLICERS	EACH	68		68	
51201600	FURNISHING STEEL PILES HP12X53	FOOT	786		786	
51202305	DRIVING PILES	FOOT	786		786	
51203600	TEST PILE STEEL HP12X53	EACH	2		2	
51204650	PILE SHOES	EACH	24		24	
51500100	NAME PLATES	EACH	1		1	
52100520	ANCHOR BOLTS, 1"	EACH	48		48	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	43		43	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	130		130	
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	575	575		
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4		
63200310	GUARDRAIL REMOVAL	FOOT	902	902		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5		
67100100	MOBILIZATION	L SUM	1	1		
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1		
<b>70001900</b>	<b>ASBESTOS BEARING PAD REMOVAL</b>	<b>EACH</b>	<b>34</b>		<b>34</b>	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10		
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1,330	1,330		
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	170	170		
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	6	6		
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2	2		
78200410	GUARDRAIL MARKERS - TYPE A	EACH	12	12		
78200520	BARRIER WALL MARKERS, TYPE B	EACH	2	2		
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	6	6		
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION, LOCATION 1	EACH	1		1	
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION, LOCATION 2	EACH	1		1	

\* SPECIALTY ITEM

 Excellence through Ownership  200 West Front Street Wheaton, IL 60187	REVISIONS NAME      DATE		ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.P. ROUTE 68 (IL 23)  <b>SUMMARY OF QUANTITIES</b>  SCALE: VERT. HORIZ. DATE: OCTOBER 20, 2006
		DRAWN BY: NC/JT/SR CHECKED BY: DWB	