


PAVEMENT MARKING SCHEDULE						
LOCATION	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL (EACH)	POLYUREA PAVEMENT MARKING - LINE 4" (FOOT)	POLYUREA PAVEMENT MARKING - LINE 6" (FOOT)	RAISED REFLECTIVE PAVEMENT MARKER (EACH)	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) (EACH)	BARRIER WALL MARKERS - TYPE B (EACH)
EASTBOUND						
STA. 526+70.00 TO 533+35.00		665				
STA. 530+48.00 TO 530+55.50						1
CENTERLINE						
STA. 526+70.00 TO 529+18.00	3		85	3		
STA. 529+18.00 TO 530+85.50			85		2	
STA. 530+85.50 TO 533+35.00	3			3		
WESTBOUND						
STA. 526+70.00 TO 533+35.00		665				
STA. 530+48.00 TO 530+55.50						1
TOTAL	6	1,330	170	6	2	2

PAVEMENT SCHEDULE								
LOCATION	SUB-BASE GRANULAR MATERIAL TYPE A 4" (SQ YD)	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE) (SQ YD)	BRIDGE APPROACH PAVEMENT (SQ YD)	PROTECTIVE COAT (SQ YD)	HOT-MIX ASPHALT SHOULDERS 6 1/2" (SQ YD)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 (TON)	LEVELING BINDER (MACHINE METHOD) N50 (TON)	BITUMINOUS MATERIALS (PRIME COAT) (SQ YD)
EASTBOUND								
STA. 526+70.00 TO 529+12.00	190				162	44	21	41
STA. 529+12.00 TO 529+18.00	2	11			2			0.25
STA. 529+18.00 TO 529+48.00	12		55	55	9			
STA. 530+55.50 TO 530+85.50	12		55	55	9			
STA. 530+85.50 TO 530+91.50	2	11			2			0.25
STA. 530+91.50 TO 533+35.00	194				166	44	16	41
WESTBOUND								
STA. 526+70.00 TO 529+12.00	174				146	44	21	40
STA. 529+12.00 TO 529+18.00	2	11			2			0.25
STA. 529+18.00 TO 529+48.00	12		55	55	9			
STA. 530+55.50 TO 530+85.50	12		55	55	9			
STA. 530+85.50 TO 530+91.50	2	11			2			0.25
STA. 530+91.50 TO 533+35.00	180				152	44	16	41
TOTAL	794	44	220	220	670	176	74	164

PAVEMENT REMOVAL SCHEDULE			
LOCATION	PAVEMENT REMOVAL (SQ YD)	APPROACH SLAB REMOVAL (SQ YD)	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT (SQ YD)
EASTBOUND			
STA. 526+70.00 TO 527+30.00			88
STA. 529+12.00 TO 529+31.79	30		
STA. 529+31.79 TO 529+61.79		43	
STA. 530+38.29 TO 530+68.29		43	
STA. 530+68.29 TO 530+91.50	31		
STA. 532+75.00 TO 533+35.00			82
WESTBOUND			
STA. 526+70.00 TO 527+30.00			87
STA. 529+12.00 TO 529+31.79	28		
STA. 529+31.79 TO 529+61.79		45	
STA. 530+38.29 TO 530+68.29		45	
STA. 530+68.29 TO 530+91.50	36		
STA. 532+75.00 TO 533+35.00			91
TOTAL	125	176	348

GUARDRAIL SCHEDULE					
LOCATION	GUARDRAIL REMOVAL (FOOT)	STEEL PLATE BEAM GUARDRAIL TYPE A (FOOT)	TRAFFIC BARRIER TERMINAL TYPE 6 (EACH)	TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (TANGENT) (EACH)	GUARDRAIL MARKERS - TYPE A (EACH)
EASTBOUND					
STA. 526+89.46 TO 529+47.68	254	162.5	1	1	3
STA. 530+50.18 TO 532+70.83	192	125	1	1	3
WESTBOUND					
527+32.71 TO 529+53.32	204	125	1	1	3
530+55.82 TO 533+13.97	252	162.5	1	1	3
TOTAL	902	575	4	4	12

EARTHWORK SCHEDULE					
LOCATION	EARTH EXCAVATION (CU YD)	SUITABLE EARTH EXCAVATION (CU YD)	EMBANKMENT (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%) (CU YD)	EARTHWORK BALANCE (+) WASTE (-) SHORTAGE (CU YD)
STA. 526+70.00 TO STA. 529+48.00	157	157	0	118	(+) 118
STA. 530+55.50 TO STA. 533+35.00	163	163	5	122	(+) 117

 Excellence through Ownership  200 West Front Street Wheaton, IL 60187	REVISIONS NAME      DATE		ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.P. ROUTE 68 (IL 23)  <b>SCHEDULE OF QUANTITIES</b>  SCALE: VERT. HORIZ. DATE: OCTOBER 20, 2006
		DRAWN BY: NC/JT/SR CHECKED BY: DWB	