

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
607	(124)TS-1	LASALLE	3	2
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

GENERAL NOTES

1. THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF ALL UNDERGROUND UTILITIES PRIOR TO BEGINNING CONSTRUCTION. (J.U.L.I.E. 800-892-0123, LASALLE COUNTY, SERENA TOWNSHIP)
2. A 1/4" DIAMETER CONTINOUS NYLON ROPE SHALL BE FURNISHED AND LEFT IN PLACE IN ALL CONDUITS BETWEEN HANDHOLES AND FLASHER CONTROLLER, AS INCIDENTAL TO THE RESPECTIVE CABLE PAY ITEMS.
3. THE CONTRACTOR SHALL CONTACT ILLINOIS POWER (800-755-5000) PRIOR TO BEGINNING WORK FOR THE UTILITY COMPANY REQUIREMENTS.

SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: Y031-1F			
CODE NO.	ITEM	UNIT	RURAL 100% STATE TOTAL QUANTITY
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
81012500	CONDUIT IN TRENCH, 1 1/2 " DIA., PVC	FOOT	970
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	225
81100500	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., GALVANIZED STEEL	FOOT	32
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	5
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1240
85000500	MAINTENANCE OF EXISTING FLASHING BEACON INSTALLATION	EACH	1
85800100	FLASHER CONTROLLER	EACH	1
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1260
88040030	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 1-SECTION, POST MOUNTED	EACH	2
X8950065	REMOVE EXISTING FLASHER CONTROLLER	EACH	1

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE

PREPARED BY: Bruce A. Hoken
DISTRICT OPERATIONS ENGINEER

DATE: 10-26-06

EXAMINED BY: R. Powell
DISTRICT STUDIES & PLANS ENGINEER

Harli Jones
DISTRICT CONSTRUCTION ENGINEER
Matt Jenks
DISTRICT MATERIALS ENGINEER

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**GENERAL NOTES
AND
SUMMARY OF QUANTITIES**

SCALE: VERT. DATE
HORIZ. CHECKED BY
DRAWN BY