


TREE REMOVAL (CONTINUED)			
STATION	OFFSET FROM CENTERLINE (FEET)	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)
		UNIT	UNIT
82+16.83	17' LT		36
82+19.35	156' LT	14	
82+22.04	118' LT	12	
82+28.91	84' LT	12	
82+32.54	136' LT	10	
82+34.75	182' LT	14	
82+35.03	164' LT		16
82+35.63	111' LT	14	
82+52.97	2' LT		36
82+96.54	8' RT		24
83+26.97	68' LT	6	
83+60.78	62' RT		16
83+63.97	30' LT	14	
83+72.34	37' LT	14	
83+78.98	149' LT	12	
83+81.29	0' RT		18
83+83.77	13' LT	12	
83+94.60	170' LT	12	
83+96.82	20' LT	12	
84+03.82	10' RT	10	
84+15.60	147' LT		20
84+27.75	26' LT	12	
84+30.71	6' RT	12	
84+71.62	49' RT		22
84+73.69	18' LT	14	
84+86.55	54' RT		16
84+95.43	56' RT		20
84+95.97	156' LT	10	
85+05.17	152' LT	10	
85+24.00	48' LT		16
85+31.52	0' RT	14	
85+76.98	37' LT	10	
85+92.06	153' LT		24
85+98.88	36' LT	10	
86+17.69	33' RT	10	
86+18.15	36' LT	8	
86+22.91	19' RT	10	
86+28.94	114' LT	10	
86+33.13	50' LT	12	
86+48.10	33' RT	10	
87+39.01	163' LT	8	
87+47.37	151' LT		24
87+57.99	28' LT	14	
115+36.08	180' RT		36
SUBTOTAL MCDONOUGH COUNTY		1537	1767
PROJECT TOTAL		1703	1887

TREE REMOVAL (ACRES)			
LOCATION STATION TO STATION	OFFSET	TREE REMOVAL	
		ACRES	
1409+05.48	1409+82.22	LT	0.12
1416+24.65	1416+91.56	LT	0.10
1430+26.42	1430+77.94	LT	0.02
1431+24.95	1432+25.28	LT	0.11
1433+35.08	1433+54.84	RT	0.01
1433+72.39	1435+74.44	RT	0.07
1440+74.80	1441+30.56	LT	0.04
1441+25.99	1442+88.62	LT	0.32
1441+35.14	1443+10.14	RT	0.40
SUBTOTAL HANCOCK COUNTY			1.25
1442+70.41	1443+06.49	LT	0.02
1442+81.97	1446+59.25	LT	0.99
1442+88.62	1447+41.78	RT	1.45
1+30.21	4+23.11	LT	0.83
9+38.07	10+65.38	LT	0.06
11+07.96	17+82.24	RT	0.80
11+13.68	12+74.24	LT	0.07
12+59.60	12+99.06	RT	0.03
12+66.31	16+61.29	LT	0.73
13+13.93	16+54.53	RT	0.29
22+16.02	25+11.26	RT	0.30
22+33.94	27+26.75	LT	1.48
22+67.41	27+29.49	RT	0.23
25+94.51	28+39.75	LT	0.41
27+76.74	28+47.93	RT	0.04
71+20.33	72+42.80	LT	0.18
71+61.34	72+03.88	LT	0.02
72+15.21	72+40.91	RT	0.01
78+64.44	80+19.31	LT	0.40
80+11.94	81+47.58	LT	0.29
88+77.31	88+89.03	LT	0.02
SUBTOTAL MCDONOUGH COUNTY			8.65
PROJECT TOTAL			10.00

PAVEMENT REMOVAL		
LOCATION STATION TO STATION	AREA SQ YD	
HANCOCK COUNTY		
IL 336		
STA 1369+85.60 TO STA 1375+50.08	1685	
STA 1400+50.00 TO STA 1413+00.00	3610	
STA 1420+00.00 TO STA 1431+36.48	3213	
STA 1433+26.55 TO STA 1434+00.00	175	
STA 1439+00.00 TO STA 1442.31.50	848	
SUBTOTAL HANCOCK COUNTY		9531
MCDONOUGH COUNTY		
IL 336		
STA 9+39.40 TO STA 22+22.15	4331	
STA 22+22.15 TO STA 48+99.10	8747	
STA 48+99.10 TO STA 75+57.07	9108	
STA 75+57.07 TO STA 115+72.45	11558	
STA 115+72.45 TO STA 122+70.50	2006	
SUBTOTAL MCDONOUGH COUNTY		41841
PROJECT TOTAL		51372

SETTLEMENT PLATFORMS		
LOCATION STATION	OFFSET	EACH
HANCOCK COUNTY		
1407+28	35' LT	1
1434+90	45' LT	1
1434+90	45' RT	1
SUBTOTAL HANCOCK COUNTY		3
MCDONOUGH COUNTY		
15+20	65' RT	1
SUBTOTAL MCDONOUGH COUNTY		1
PROJECT TOTAL		4

BUILDING REMOVAL								
BUILDING NO.	STATION	OFFSET	SIDE	DESCRIPTION	BUILDING REMOVAL	REMOVAL & DISPOSAL OF FRIABLE ASBESTOS	REMOVAL & DISPOSAL OF NON-FRIABLE ASBESTOS	
HANCOCK COUNTY					LUMP SUM	LUMP SUM	LUMP SUM	
1	1422+33	114'	RT	HOUSE	1	1	1	
2	1429+35	115'	RT	HOUSE	1			
3	1430+16	127'	RT	GARAGE	1			
MCDONOUGH COUNTY								
4	55+83	98'	LT	HOUSE	1		1	
5	REMOVED FROM CONTRACT							
6	73+06	30'	LT	SHED	1			
7	73+12	120'	LT	SHED	1			
8	73+12	120'	LT	SHED	1			
9	73+54	22'	RT	HOUSE	1			
10	73+85	133'	LT	SHED	1		1	
11	74+27	60'	LT	GARAGE	1			
12	74+80	62'	LT	SHED	1			
13	74+80	62'	LT	SHED	1			
14	75+41	36'	LT	AG BIN	1			
15	75+41	57'	LT	AG BIN	1			
16	73+52	60'	LT	SHED	1			
17	73+03	52'	LT	SHED	1			



△ REVISED 11/1/06

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 TREE REMOVAL (cont),
 PAVEMENT REMOVAL, BUILDING
 REMOVAL & SETTLEMENT PLATFORMS
 SCALE: VERT. N/A
 HORIZ. N/A
 DATE 11/9/05
 DRAWN BY BDS
 CHECKED BY SRD

Plot Date: 8/20/2006
 Plot Time: 2:46:43 PM
 Plotted By: sdonahue
 Pen Table: ldot.tbl
 Filename: I:\2003\cadd\construction\plans\007.sch\sheet31.dgn