

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
701	(128BR1-1	TAZEWELL	29	5
STA. 77+63.98		TO STA. 78+48.02		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

# SUMMARY OF QUANTITIES

## CONSTRUCTION TYPE CODE

CODE NO.	ITEM	UNIT	CONSTRUCTION TYPE CODE		TOTAL
			X080-2A	SFTY-3N	
			STATE 100% →		
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
50300225	CONCRETE STRUCTURES	CU YD	6		6
50300260	BRIDGE DECK GROOVING	SQ YD	273		273
50300300	PROTECTIVE COAT	SQ YD	294		294
50400105	PRECAST CONCRETE BRIDGE SLAB	SQ FT	299		299
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS ( 21" DEPTH)	SQ FT	2646		2646
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4,640		4,640
50800515	BAR SPLICERS	EACH	88		88
50901050	STEEL RAILING , TYPE SM	FOOT	244		244
51500100	NAME PLATES	EACH	1		1
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	37.5		37.5
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4		4
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL ( TANGENT)	EACH	4		4
63200305	STEEL PLATE BEAM GUARDRAIL REMOVAL <i>EXISTING</i>	FOOT	125		125
63300205	REMOVAL AND REINSTALLATION OF STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	50		50
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4		4
67100100	MOBILIZATION	LSUM	1		1
70100405	TRAFFIC CONTROL AND PROTECTION STANDARD 701321	EACH	1		1
70104600	TRAFFIC CONTROL AND PROTECTION STANDARD 701306	L SUM	1		1

\* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 SCALE: VERT. \_\_\_\_\_  
 DATE 03-24-2006  
 DRAWN BY CEJ  
 CHECKED BY \_\_\_\_\_