

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEET NO.
474	(72-28)I	PEORIA	26
STA. 56+57.18 TO STA. 58+86.79			3
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

100% STATE SAFETY - 2A
PEORIA COUNTY

CODE NO.	ITEM	UNIT	URBAN	TOTAL
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	106	106
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	312	312
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX 'D', N70	TON	104	104
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	2700	2700
44004250	PAVED SHOULDER REMOVAL	SQ YD	930-1816	930-1816
50102400	CONCRETE REMOVAL	CU YD	36.2	36.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	36.2	36.2
50300260	BRIDGE DECK GROOVING	SQ YD	2670	2670
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4860	4860
50800515	BAR SPLICERS	EACH	40	40
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	2	2

△ REVISIED 1/5/07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.
DATE 07-07-2006

DRAWN BY CEJ
CHECKED BY

PLT DATE
SCALE
REFERENCE