

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
474	(72-2HB)I	PEORIA	26	7
STA. 56+57.18 TO STA. 58+86.79				
FED. ROAD DIST. NO. 4 ILLINOIS			FED. AID PROJECT	

SCHEDULE OF QUANTITIES

MOBILIZATION

JOBSITE = 1.0 LSUM

T, C, & P, STANDARD 701 400

JOBSITE = 1.0 LSUM

T, C, & P, STANDARD 701 401

JOBSITE = 1.0 LSUM

SUB-BASE GRANULAR MATERIAL

GORE/SHOULDER = 106 TON

HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70

= 312 TON

HOT-MIX ASPHALT SURFACE COURSE, MIX 'D', N70

= 104 TON

TEMPORARY CONCRETE BARRIER

JOBSITE WORKING AREA = 1392 FOOT

WORKZONE PAVEMENT MARKING REMOVAL

RAMP 'B' = 1500 SQ. FT.

PAVEMENT MARKING TAPE, TYPE III, 4''

JOBSITE WORKING AREA = 800 FOOT

TEMP. PAVEMENT MARKING LINE, 4''

JOBSITE WORKING AREA = 1000 FOOT

CHANGEABLE MESSAGE SIGN

AHEAD OF RAMP 'B' = 25 DAY

PAVED SHOULDER REMOVAL

RAMP 'B' GORE AREA = 1816 SQ. FT.

IMPACT ATTENUATORS, TEMPORARY(NRD), TEST LEVEL 3

JOBSITE BRIDGE DECK AND ENTRANCE TAPER = 2 EACH

T. C. & P. STANDARD 701 402

JOBSITE = 1.0 LSUM

T. C. & P. STANDARD 701 402(SPECIAL)

JOBSITE = 1.0 EACH

PLOT DATE * NOTES
FILE NAME * FILE#
PLOT SCALE * NSCALE*
REFERENCE * REF#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE 08-08-06

DRAWN BY CEJ
CHECKED BY