

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
474	(72-2HB)I	PEORIA	26	8
STA. 56+57.18		TO STA. 58+86.79		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

SCHEDULE OF QUANTITIES

CONCRETE REMOVAL

STRUCTURE JOINTS = 36.2 CU. YD.

REINFORCEMENT BARS, EPOXY COATED

ALL STRUCTURE JOINTS = 4860 POUNDS

PREFORMED JOINT STRIP SEAL

ALL STRUCTURE JOINTS = 284 FOOT

BAR SPLICERS

BRIDGE JOINTS = 40 EACH

CONCRETE SUPERSTRUCTURE

BRIDGE JOINTS = 36.2 CU. YD.

HOT-MIX ASPHALT CONCRETE REMOVAL (DECK)

JOBSITE = 2700 SQ. YD.

BR. DECK HYDRO-SCARIFICATION (1/2)''

JOBSITE = 2700 SQ. YD.

BRIDGE DECK LATEX CONCRETE OVERLAY

JOBSITE WORKING AREA = 2700 SQ. YD.

RELOCATE TEMPORARY CONCRETE BARRIER

JOBSITE WORKING AREA = 1392 FOOT

IMPACT ATTENUATORS, RELOCATE(NRD), TEST LEVEL 3

JOBSITE BRIDGE DECK AND ENTRANCE TAPER = 2 EACH

BRIDGE DECK GROOVING

JOBSITE BRIDGE DECKS = 2670 SQ. YD.

EPOXY MARKING - LINE, 4''

JOBSITE BRIDGE DECKS = 800 FOOT

EPOXY MARKING - LINE, 6''

BRIDGE DECK SKIP-DASH = 600 FOOT

EPOXY MARKING - LINE, 8''

LANE EDGE TAPERS = 800 FOOT

PLOT DATE * * * * *
 FILE NAME * * * * *
 PLOT SCALE * * * * *
 REFERENCE * * * * *

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p style="text-align: center;">SCHEDULE OF QUANTITIES</p> <p>SCALE: VERT. DRAWN BY CEJ HORIZ. CHECKED BY DATE 08-08-06</p>