COMMITMENTS

Commitments are not to be altered without the written approval of all parties to which the commitment was made.

ENVIRONMENTAL REVIEWS

Prior to the use of any proposed borrow areas, use areas (temporary access roads, detours, run-arounds, etc.) and/or waste areas, the Contractor shall file the required environmental resource request surveys according to Section 107.22 of the Standard Specifications. These surveys are required in order for the Department to conduct cultural and biological resource surveys for the proposed site.

Prior to any waste materials being removed from the construction site the required environmental resource surveys will need to be obtained and filed by the Contractor. Excess waste products removed from the construction site shall be disposed of as required in Section 202.03 of the Standard Specifications.

Any protruding metal bars shall be removed prior to the disposal of broken concrete at approved disposal sites.

The required environmental resource documentation shall include the following:

- * BDE Form 2289 (Environmental Survey Request)
- * A location map showing the size limits and location of the use area
- * Signed property owner agreement form
- * Color photographs depicting the use area

Please note that a minimum of two weeks shall be allowed for the District to obtain the required environmental clearances.

ENGINEERS FIELD OFFICE

F.A.P. SECTION COUNTY TOTAL SHEETS NO.

645 (105BR) BR MARSHALL Q 2

STA. TO STA.

Add the following sentence to the end of paragraph 670.02 (i) and 670.04 (e): All of the telephone lines provided shall have unpublished numbers.

BITUMINOUS CONCRETE MIXTURE REQUIREMENTS

Mixture Use(s):	Bituminous Surface Course		
RAP % (Max)**:	15%		
AC/PC:	PG64-22		
Design Air Voids:	4.2% @ N = 50		
Mixture Composition:	IL 9.5 or 12.5		
(Gradation Mixture)			
Friction Aggregate	Mix D		

** If the RAP option is selected, the asphalt cement grade may need to be adjusted; this will be determined by the Engineer.

Maintenance costs for temporary bridge traffic signal installation shall be paid for separately in accordance with Article 109.04

Traffic Control Standard 701316 is currently in place and shall be modified in accordance to Traffic Control Standard 701321. (See Traffic Control Standard 701316 for informational use only)

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATIO			
NAME	DATE	ILLINOIS DEFARIMENT OF TRANSPORTATIO			
		GENERAL			
		NOTES			
		SCALE: VERT, HORIZ.	DRAWN BY BTS		
		DATE 10-11-2006	CHECKED BY		