

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	13R,3X1RS	CHAMPAIGN	47	4

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE:
LOCATION OF WORK:

URBAN
80% FED.
20% STATE
I000-2A
STA. 169+60 TO 16+08
FAP 808
US 150
QUANTITY

URBAN
80% FED.
20% STATE
I000-2A
STA. 16+08 TO 58+98.62
FAP 808 SPUR
IL 130 SPUR
QUANTITY

CODE NO	ITEM	UNIT	TOTAL QUANTITY	URBAN 80% FED. 20% STATE I000-2A STA. 169+60 TO 16+08 FAP 808 US 150 QUANTITY	URBAN 80% FED. 20% STATE I000-2A STA. 16+08 TO 58+98.62 FAP 808 SPUR IL 130 SPUR QUANTITY
20200100	EARTH EXCAVATION	CU YD	10.0	10.0	0.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	9110.0	6764.0	2346.0
40600300	AGGREGATE (PRIME COAT)	TON	183.0	136.0	47.0
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20.0	12.0	8.0
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD) N90	TON	2074.0	1884.0	190.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0	1.0	0.0
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	710.0	710.0	0.0
40600990	TEMPORARY RAMP	SQ YD	886.0	886.0	0.0
40803545	POLYMERIZED HOT-MIX ASPHALT SURFACE, MIX "D", N90	TON	4889.0	3002.0	1687.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	54.0	54.0	0.0
40800030	AGGREGATE (PRIME COAT)	TON	2.0	2.0	0.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	60.0	60.0	0.0
44000154	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4"	SQ YD	16689.0	0.0	16689.0
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	10404.0	7020.0	3384.0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	143.0	143.0	0.0
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	24.0	24.0	0.0
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	5947.0	5947.0	0.0
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	24.0	24.0	0.0
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	163.0	163.0	0.0
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	145.0	32.0	113.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	78.0	12.0	66.0
48203007	HOT-MIX ASPHALT SHOULDERS, 2 1/2"	SQ YD	434.0	234.0	200.0
60255500	MANHOLES TO BE ADJUSTED	EACH	6.0	6.0	0.0
60261300	INLETS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	12.0	5.0	7.0
60266600	VALVE BOXES TO BE ADJUSTED	EACH	6.0	6.0	0.0
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	19.0	19.0	0.0
60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	28.0	28.0	0.0
60402510	GRATES, TYPE 11	EACH	42.0	42.0	0.0
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	650.0	650.0	0.0
60622353	CONCRETE MEDIAN, TYPE SM-6	SQ FT	223.0	223.0	0.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3.0	1.5	1.5

PLOT DATE * 10/27/2008
 FILE NAME * s:\projects\70122\70122.dgn
 USER NAME * jk2008 / JL
 USER NAME * jk2008 / JL